

COPY OILFIELD RESEARCH LABORATORIES

P.O. BOX 647 - 536 N. HIGHLAND - CHANUTE, KS 66720 - PHONE (316) 431-2650 - FAX (316) 431-2671

July 20, 1992

Lancer Oil, Inc.
P. O. Box 34
Piqua, Kansas 66761

Gentlemen:


Attached hereto are the results of tests run on the rotary core taken from the Taylor Lease, Well No. P-6, located in Section 23, T28S, R18E, Neosho County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client and submitted to our laboratory on July 6, 1992.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES


Alan M. Dunning

AMD:bl

5 c Piqua, KS

RECEIVED
STATE CORPORATION COMMISSION

AUG 31 1992

CONSERVATION DIVISION
Wichita, Kansas

- REGISTERED ENGINEERS -

CORE ANALYSIS - WATER ANALYSIS - REPRESSURING ENGINEERING - SURVEYING & MAPPING - PROPERTY EVALUATION & OPERATION

LOG

Company Lancer Oil, Inc. Lease Taylor Well No. P-6

BARTLESVILLE SANDSTONE

<u>Depth Interval, Feet</u>	<u>Description</u>
765.0 - 765.2	Sandstone and shale, light gray and gray, laminated.
765.2 - 767.0	Sandstone, light brown.
767.0 - 768.3	Sandstone, light brown with widely scattered shale and mica inclusions.
768.3 - 772.0	No core received.
772.0 - 775.0	Sandstone, light brown, shaly with widely scattered shale and mica inclusions.
775.0 - 775.5	Sandstone, light brown.
775.5 - 781.5	No core received.
781.5 - 783.0	Sandstone, light brown, very shaly with widely scattered shale and mica inclusions.
783.0 - 784.0	Sandstone, light brown, slightly shaly with widely scattered shale and mica inclusions.

RECEIVED
STATE CORPORATION COMMISSION

AUG 31 1992

CONSERVATION DIVISION
Wichita, Kansas

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1

COPY

Company Lancer Oil, Inc. Lease Taylor Well No. P-6

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A. Ft.	Permeability, Millidarcys
			Oil	Water	Total		
1	765.4	17.4	31	57	88	419	20.
2	766.5	18.7	33	49	82	479	21.
3	767.5	18.4	23	54	77	328	9.4
4	772.6	14.0	17	81	98	185	0.39
5	773.6	15.0	23	68	91	268	1.2
6	774.5	17.1	30	68	98	398	3.8
7	775.4	20.5	15	65	80	239	28.
8	781.7	14.5	24	63	87	270	0.44
9	782.6	14.8	16	64	80	184	1.1
10	783.4	17.6	23	62	85	314	6.8

RECEIVED
STATE CORPORATION COMMISSION

AUG 31 1992

CONSERVATION DIVISION
Wichita, Kansas