

508 East Murdock,

Wichita, Kansas

27-28-18E

Company- CREEK OIL & GAS CO., INC.

Farm- Wells

No. 7

SEC. 27 T. 28 R. 18E

SE NW SE NW

1755' FWL, 1670' FNL

County Neosho

KANSAS

Total Depth. 840'

Comm. 8-26-57

Comp. 9-4-57

Shot or Treated.

Contractor, J.W. Fisher

Issued. 12-3-60

CASING:

6 5/8" 660' P
 4 1/2" 839' w/45 sx cem.

Elevation. 984'

Production. OIL

Figures indicate Bottom of Formations.

soil	1
sandstone, clay	9
shale	81
limest ne	87
shale	105
limestone	170
shale	218
limestone	237
shale	242
limestone	254
shale	268
limestone	322
shale	347
limestone, shells	352
shale	383
limestone, shells	395
shale	411
limestone	423
shale	500
limestone	553
shale	597 1/2
limestone	618
shale	635
limestone	639
shale	676
limestone	679
shale	725
limest ne	727
shale	778
limestone	779
shale, sdy	799

CORED @ 796'

sandstone, oil, few	
shale stks	828
shale, w/carb. ss.	840
Total Depth	

T.O.P.S:

Pawnee ls	500
Labette	553
Ft. Scott ls.	597 1/2
Cherokee sh	639
Bartlesville	799

Zone Completed; Bartlesville ss.