

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

27-28-18E

Company- CREEK OIL & GAS CO., INC.

Farm- Wells

No. 6

SEC. 27 T. 28 R. 18E

SW NE SE NW

2200' FWL, 1765' FNL

Total Depth. 837'

Comm. 8-16-57

Comp. 8-24-57


Shot or Treated.

Contractor. J.W. Fisher

Issued. 12-3-60

County Neosho

KANSAS



CASING:

Elevation. 981'

Production. OIL

Figures indicate Bottom of Formations.

10" 8'
6 5/8" 651' P
4 1/2" 837' w/50 sx cem.

soil	2
sdv clay	5
sand rock	12
shale	100
lime	162
shale, sdv	166
lime	175
sand,	205
shale	215
lime	230
shale	235
lime	247
shale, sand	263
lime	315
shale	375
sand	395
shale	408
lime	416
shale	494
lime	545
shale	591
lime	612
shale	621
lime	625
shale, sdv	645
shale	672
lime	676
shale	717
lime	719
shale	772
lime	773
shale	780
shale, sdv	787
shale, sdv, show oil	791
CORED @ 791'	
shale, sdv, show oil	796
sandstone, brkn, oil	803
shale	807
sandstone, oil	831
sandstone, brkn	832
sandstone, shaley	833
shale, sdv	834
sandstone, carb. &	
Conglomerate	837
Total Depth	

TOPS:

Pawnee ls.	494
Labette	545
Ft. Scott ls.	591
Cherokee sh	625
Bartlesville	796