

27-28-18E


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CREEK OIL & GAS CO., INC.
Farm- Wells No. 15

SEC. 27 T. 28 R.18E
SE NE SW NW
1240' FWL & 1880' FNL

Total Depth. 822'
Comm. 12-23-57 Comp. 12-27-57
Shot or Treated.
Contractor. Cogco Drlg. Co.
Issued. 12-31-60

County Neosho
KANSAS



Elevation. 973'

Production. Oil (Converted to
Wtr. Inj.)

Figures Indicate Bottom of Formations.

soil, sandstone	6
shale	69
limestone	79
shale	91
shale, w/l's stks	113
limestone, w/sh stks	158
shale	210'
limestone	228
shale	235
limestone	241
shale	260
limestone	314
shale	375
limestone	393
shale	409
limestone	416
shale	496
limestone	542
shale	582
limestone	604
shale	613
limestone	618
shale	664
limestone	667
shale	713
limestone	715
shale	782
CORED @ 782'	
sandstone, brkn, oil	796
sandstone, oil	814½
sandstone, brkn, oil	816
sandstone, oil	821
coal	821½
shale	822
Total Depth	

TOPS:

Pawnee Ls.	496
Labette	542
Ft. Scott	582
Cherokee sh	618
Birtlesville	782