

Company Paul Ruf

Sec. 24 T. 10 N. E. 23 E
Loc. 300' N - 1560' W of SWc

Plotted


Farm Wahlin Estate No. 4

24-10-23E

Total Depth 583 1/2
Conn.
Shot or Treated
Contractor
Issued

Comp. 10/31/30

County Wyandotte



Elevation 922 ^{OK}
930.5 Ruf NS tie
Production 3/4 M cu. ft. gas

Casing

20 in.	10 in.
15 1/2	8 1/4
12 1/2	6 5/8
13 3/8	5 3/16

Figures Indicate Bottom of Formation

soil	5	lime	464
boulders	10	shale blue	479
sand	20	lime	485
shale	25	sand	500 gas
lime	42		
shale	66		
lime	73		
shale	76		
lime	80		
shale	82		
lime	91		
shale	112		
lime	140		
shale	145		
lime	154		
shale	167		
lime	174		
shale	176		
lime	192		
shale	209		
lime	211		
shale	212		
lime	216		
shale	223		
lime	228		
shale	230		
lime	251		
shale black	255 water		
lime	275		
shale	278		
lime	281		
shale	284		
lime	293 Hertha		
shale	305		
sand	315 75 M cu. ft. gas		
shale	402		
lime	407		
red bed	412		
sand	425		
shale	440		
lime	441		
shale	462		

T.D.

This well deepened 583 1/2
1560' E of WL, 300' N of SL (NE SW SE SW)
Comp. 1/30/31
1,360,000 cu. ft. gas
200 # FP
4 3/4" packer set at 25' up the hole
Screw packer

sand Peru	495 gas
shale	510
lime	513
shale	516 water & gas
lime	525
shale	536
lime	538
shale	546
lime	550
shale	552
lime	553
shale	556
shale white sandy	560
sand	565 gas
sand	570 554,000 cu. ft. SA
sand	575 gas
sand	583 1/2

T.D.

244