

Company Paul Ruf

25-10-23E

Sec. 25 T. 10 R. 23 E
Loc. 700' N- 460' W Sec

Farm G. Bellamy

No. 1

Total Depth 515

Comm. 4/9/30


Shot or Treated

Contractor

Issued

Comp. 4/21/30

County Wyandotte



Casing

20 in.

15 1/2

12 1/2

13 3/8

10 in.

8 1/4 -- 41'

6 7/8 1/4" -- 220'

5 3/16 4 7/8" -- 440'

Elevation 833

Production 175,000 cu. ft. Gas
205# HP

Figures Indicate Bottom of Formation

soil	12	shale grey	374
boulders	16	lime	376
lime grey	33	shale black	377
shale grey	36	shale grey	382
lime grey	41	lime grey	383
shale grey	64	shale blue	385
lime light	74	lime	387
shale light	87	shale blue	395
lime grey	100	lime grey sandy	402
shale grey	103	sand grey	410 show oil & gas
lime grey	105	shale blue	420
shale grey	106	lime hard dark	425
lime grey	119	shale blue	428 HFW
shale grey	132	lime grey	437
lime grey	134	shale black	438
shale light	136	shale grey	455
lime grey	139	shale blue	460
shale grey	142	sand grey	470 water
lime hard	150	shale sandy grey	488
shale dark	152	sand grey	490
lime grey	173	sand grey	515 Gas
shale black	174		
shale white	180		
lime grey & blue	182		
lime grey	204		
shale grey	208		
lime grey	217		
shale grey sandy	228	show of gas	
shale sandy grey	235	show of oil & gas	
shale grey	255		
shale dark	260		
sand dark	265		
shale blue	315		
sand grey	325	show of gas	
shale grey	330		
red bed	335		
sand hard	345		
shale grey	354		
shale sandy	355		
shale grey	360		
lime	362		

T.D.

Log Plotted