

25-10-23E  
 card made out


A. E. JUDD (Commerce Drlg. Co.)  
 G. Bellamy No. (3) 1.

SEC. 25 T. 10 R. 23E  
 NE SE NW SE  
 2000' N 1660' W SE Cor.

Total Depth. 633'  
 Comm. 4-10-30 Comp. 4-24-30  
 Shot or Treated.  
 Contractor.  
 Issued. 8-6-38

County. Wyandotte

AUG 6 1938



CASING:

Elevation. 849

Production. Gas.

*Dry*

Figures Indicate Bottom of Formations.

soil	10		
sand	12	shale drk wtr	437
lime shells	14	shale sdy	440
shale grey	40	shale	450
lime	63	lime wh	453
shale grey	76	shale grey	463
lime	83	shale blk	470
shale grey	98	shale grey	476
lime	109	lime	480
shale grey	116	shale drk	485
lime	125	shale sdy	490
shale grey	144	lime grey	498
lime	150	shale grey lgt	508
shale grey	155	shale sdy	510
lime hrd	160	sand	518
shale grey	162	shale sdy grey	531
lime	183	sand water	570
slate blk wtr	185	shale grey	575
shale grey	190	shale blk	580
lime	207	shale grey	585
slate blk	210	shale drk	630
lime	212	no log	633
shale grey	214	Total Depth.	
lime Hertha	223		
shale lgt	234		
red bed	235		
sand	239		
shale grey	332		
shale lime grey	340		
show of gas			
red bed	348		
lime	350		
shale grey	370		
lime	375		
shale grey	390		
lime	400		
shale grey	409		
lime	414		
sand sh oil	428		
67,936 cu ft gas	414		

*Plotted log*