

State Geological Survey

WICHITA BRANCH

15-133-20851


KANSAS DRILLERS LOG

API No. 15 — 133 — 20,851
County Number

S. 36 T. 28 R. 18 E
Loc. 500' SNL & 160' EWL NW

County Neosho

640 Acres
N



Locate well correctly

Elev.: Gr. _____

DF _____ KB _____

Operator
D & V Oil, Inc.

Address
17 McArthur St., R. R. #3 Iola, Kansas 66749

Well No. #V-2 Lease Name Yockey Lease

Footage Location
500' feet from (N) line 160 feet from (W) line

Principal Contractor Jerry Phillips Geologist

Spud Date 2-23-78 Total Depth 748 P.B.T.D.

Date Completed 2-25-78 Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE		6 1/4"					
PRODUCTION	4 3/4"	2"	3.75	747	PORTLAND	86	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		702.5-711.25
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
25 SACKS 20-40 SAND	702.5-711.25

INITIAL PRODUCTION

Date of first production _____ Producing method (flowing, pumping, gas lift, etc.) _____

RATE OF PRODUCTION PER 24 HOURS
Oil _____ Gas _____ Water _____ Gas-oil ratio _____
bbls. MCF bbls. CFPB

Disposition of gas (vented, used on lease or sold) _____ Producing interval (s) _____

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No.	Lease Name		
S____T____R____E____W			
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
COPY ENCLOSED			
- 100 100 GOOD RUN GRIND UP 1 1/2" RUNG ALUMINUM			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received.	Signature Title Date		

P L DRILLING, Inc.

36-28-18E

P. O. BOX 350 • 1212 N. SANTA FE
CHANUTE, KANSAS 66720

D & V Oil Company
17 McArthur
Tola, Kansas 66749

36-28-18E
Date: February 23, 1978
Lease: Vockey #2
Well Size: 4 3/4"
Surface Pipe: 6 1/4"

Driller: Steve Channel
County: Neosho
Rig: #5

0 - 8	Soil	8 ft.
8 - 16	Clay	8
16 - 21	Lime	5
22 - 110	Lime w/few brks	98
110 - 120	Lime	10
120 - 130	Shale	10
130 - 180	Lime w/brks (Hard)	50
180 - 210	Lime (Hard)	30
210 - 230	Shale w/brks	20
230 - 270	Shale	40
270 - 280	Lime	10
280 - 300	Shale	20
300 - 360	Shale w/brks	60
360 - 380	Shale w/brks	20
380 - 390	Lime	10
390 - 420	Lime w/brks	30
420 - 450	Shale w/brks	30
450 - 505	Shale w/brks	55
505 - 510	Lime	5
510 - 520	Lime (Hard)	10
520 - 672	Shale w/brks	152
672 - 674	Sandy Shale	2
674 - 694	Sandy Shale w/strong odor	20
694 - 714	Core #1 LAMINATED SAND & SHALE	20
714 - 720	Shale w/coal streak, little black Sand	6
720 - 725	Shale w/brks	5
725 - 730	Black Shale	5
730 - 735	Shale	5
735 - 748	Grey Shale	13

T.D. 748 ft.