

9-8-60

Daley Heirs  
Well No. 1.

State of Kansas  
Neosho County  
Northeast quarter of Northeast quarter  
Section 19-28-18  
1100' from East line of quarter section  
400' from North line of quarter section

<u>Thickness of Strata</u>	<u>Formation</u>	<u>Total Depth</u>	<u>Remarks</u>
29	Sandy Shale	750	
38	Dark Shale Sandy	788	
2	Broken Sand	790	
4	Oil sand	794	Good show fine broken sand
3.5	Oil sand	797.5	" " " " "
3.6	Oil sand	801.1	" " " " "
1.1	Oil sand	802.2	" " " " "
2.9	Oil sand	805.1	Show -Darker fine sand
	Total Depth	805.1	

1-4 7/8" Clayton packer set @ 790'  
1-2" Seating nipple set @ 787'  
5 sacks cement run on packer

Material used in Hole:

- 23' of 8 1/4" drive pipe
- 807.1' of 2" tubing
- 802.9' of 1" tubing
- 1-4 7/8" Clayton packer
- 1-2" Seating nipple
- 1-2" Cage
- 1-2" Perforation
- 1-2" Working barrel

