

Company Ruf Drilling Co.

Sec. 25 T. 10 S. 23 E  
Loc. 230' E of WL, 1290' S of NL  
(SW NW RW)

*Plotted*


Farm C. H. Brunker No. 3

25-10-23E

Total Depth 631 1/2  
Comm. 4/17/31  
Shot or Treated  
Contractor  
Issued

Comp. 4/27/31

County Wyandotte



Elevation 963

Production 1,571,000 cu. ft. gas  
RP 180#

Figures Indicate Bottom of Formation

soil & clay	20	shale	343
sand rock	30	red bed	347
lime	38	shale	358
shale	42	sand	361 little gas
lime	47	shale	447
shale	65	sand	451
lime	78	red bed	456
shale	79	lime sandy	461
lime	82	shale	480
shale black	83 little water	lime	482
sand	93	sand	485
shale	104	shale	501
lime	114	lime	506
shale	118	shale	511
lime	125	sand hard	512
shale	153	shale	520
lime	181	lime	522 Peru
shale	188	sand	524 Peru
lime	193	lime	525
shale	195	sand	526
lime	197	shale white	530 Gas
shale	208	sand	538 Gas
lime	219	shale	546
shale	222	lime <i>lex</i>	549 Water & gas
lime	238	shale black	550 Water & gas
shale	255	shale grey	553
lime	257	lime sandy	556
slate black	258 little water	shale	558
lime	260	lime	562
shale	268	shale	574
lime	275	lime	576 water
shale	278	shale black	578 Water 82 1/2
lime	297	shale grey	584 SIM 582 1/2
shale	298	lime	588
lime	299	shale	596
shale	305	sand Gas	631 1/2
lime	320		
slate black	322		T.D.
lime	326		
shale grey	335		
lime ( <u>Hertha</u> )	340		

Packer set at 600'

*Plotted Log*