

Company Chas. T. Judd.

Sec. 25 T. 10 E. 23 E *Plotted*
Loc. 600' S, 2200' E NWC
(SW NE NE NW)

Farm Winters


No. 1

Total Depth 538
Comm. 6/17/30
Shot or Treated
Contractor
Issued

Comp. 6/28/30

County Wyandotte

25-10-23E



Elevation 975.

Production 1,691,000 cu. ft. gas

Figures Indicate Bottom of Formation

soil & clay	15	
sand	18	
sandy clay	28	
opening	32	
lime	44	
shale black	49	
lime	53	
shale grey	70	
lime	85	
shale grey	108	
lime	128	
shale grey	160	
lime	193	
shale blue	200	
lime	204	
shale dark grey	215	
lime	224	
shale grey	228	
lime	240	
shale grey dark	270	
lime	298	
slate black	303	gas
lime	322	
slate black	327	30,000 cu. ft. gas
lime <i>Hertha</i>	341	
shale grey	351	
red bed	354	
shale grey	442	
sand	452	show gas
red bed	457	
lime	467	
shale grey	495	
lime	496	
sand	502	
lime	507	
shale dark grey	521	
lime	525	
sand	530	554,000 cu. ft. gas
"	534	1,300,000 " "
"	536	1,460,000 " "
"	537	1,470,000 " "
"	538	1,691,000 " "

T.D.

Perm

Plotted Log