

Company Chas. T. Judd

Sec. 25 T. 10 S. 23 E Plotted  
Loc. 500' S & 1400' E of NWC  
(SW NE NE NW)

Farm Winters


No. 2

25-10-23E

Total Depth 610½  
Conn.  
Shot or Treated  
Contractor  
Issued

Comp. 8/26/30

County Wyandotte



Casing  
20 in. 10 in.  
15 1/2 8 1/4  
12 1/2 6 5/8  
13 3/8 5 3/16

Elevation 945

Production 800,000 cu. ft. gas

Figures Indicate Bottom of Formation

surface clay 15  
slate black 19  
lime 26  
shale grey 42  
lime 58  
lime broken 65  
shale grey 85  
lime 90  
shale grey 95  
lime 105  
shale grey 127  
lime 155  
shale grey 161  
lime 171  
shale dark grey 184  
lime 195  
shale blue 198  
lime 211  
shale grey dark 228  
lime 235  
shale grey 240  
lime 246  
shale dark grey 252  
lime 270  
slate black 275  
shale grey 278  
lime 295  
slate black 299 water  
lime *Hertha* 312  
shale grey 317  
red bed 320  
shale grey 336  
sand 340 show of gas  
shale grey sandy 415  
sand 422  
red bed 427  
lime 437  
shale grey 469  
sand 475 show of gas  
lime 480  
slate black 482

lime 485  
shale grey 494  
lime 498  
shale sandy white 509  
sand 510

Note: 1st hole was lost at this depth; second hole drilled 30 ft. east, surface elevation 945'; drilled to 519' TD; shut in for 800,000 cu. ft.

Deepened from 519' to 610½' March 21, 1931  
1,900,000 cu. ft. gas  
190# RP

*Lax* lime hard grey 523  
slate 529  
lime 535  
shale grey 538  
shale black 541  
shale light grey 554  
lime grey hard 555  
shale grey 565 SLM 565  
lime grey hard 567  
shale grey 571  
shale sandy white 575  
lime sandy broken 579  
sand 610 ) 52 21'  
lime hard 610½

T.D.

Plotted Log