

34-10-236

Company Quindaro Gas Co.

Sec. 34 T. 10 R. 23E

Loc. SE SW NE NE

County Wyandotte

680' WEL  
1100' SNL

Farm Ditzen

No. 2

Total Depth 651


Comm. 2-10-31

Shot or Treated

Contractor

Issued 1-19-35

Comp. 2-20-31



Casing

20 in.	10 in.
15 1/2	8 1/4 30
12 1/2	6 5/8 482
13 3/8	5 3/16

Elevation 965

Production Dry

Figures Indicate Bottom of Formation

soil	15	shale grey	368
sandstone	28 wtr	sand	373
lime	38	shale sdy	380
shale blue	42	shale grey	397
lime	55	sand	409
shale dark	60	shale sdy	424
lime	64	shale grey	456
shale grey	85	sand	466-SLM - 460
lime	104	shale grey	468
lime broken	110	red bed	470
lime	126	shale green	473
shale grey	132	sand	478
lime broken	138	shale grey	491
shale sdy	155	lime sdy	501
shale blue	166	shale sdy	510
lime	195	shale and lime	516
shale blue	200 SLM	lime sdy	523
lime	205	shale grey	536
shale blue	207	lime	542
lime	209	shale grey sdy	553
shale drk	212 little wtr.	shale dark	562
shale grey	217	lime Lex	566
lime	227	shale dark	570 wtr
shale grey	233	lime sdy	578
lime	247	lime	582
shale blue	265	shale grey	588
lime broken	270	lime	592
shale blue	275	shale dark	598
lime	280	shale grey	611 SLM 602
lime broken	286	lime	614
lime	306-SLM 304	shale dark	616
shale blue	314	shale grey	626
lime	335	lime sdy	629
slate blk	338 wtr	sand and shale	635 oil show
shale blue	345	shale grey sdy	651 TD. SLM
lime Hertha	353		

