

Company Currence

Farm Cunningham

No. 1

Total Depth 667 $\frac{1}{2}$

Comm.

Shot or Treated

Contractor


Issued

Comp. 8/15/31

Sec. 35 T. 10 R. 23 E
Loc. 1050' fr EL, 2600' fr SL SE $\frac{1}{2}$

35-10-23 *plotted*

County Wyandotte



Elevation ~~905~~
1005 on streets

Production Very light well

Casing	
20 in.	10 in.
15 1/2	8 1/4
12 1/2	6 5/8
13 3/8	5 3/16

Figures Indicate Bottom of Formation

soil	5	shale	518
sand	25	lime	520
lime	36	shale	522
shale	40	sand, water	528
lime	55	shale	530
shale, water	57	sand	536
lime	62	shale	538
shale	72	lime	543
lime	97	shale	553
shale	117	lime	560
lime	126	shale	565
shale	130	lime	572
lime	138	shale	585
shale	162	lime <i>Lex</i>	587
lime	193	shale black, gas show	593
shale	200	lime	596
lime	209	shale	598
shale	225	lime	600
lime	235	shale dark, gas show	605
shale	239	shale sandy	620
lime	245	sand dry	625
shale	247	sand, gas show	667 $\frac{1}{2}$
lime	255		
shale	267		
lime	274		
shale dark	278		
lime	308		
shale dark, water	311		
lime	333		
shale	337		
lime <i>Nevha</i>	352		
shale dark, water	362		
shale sandy	377 ?		
shale	395		
shale sandy	405		
shale	460		
lime sandy, gas show	468		
red rock	472		
shale	488		
shale green & red	498		
sand, oil & gas show	513		

T.D.