

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bank Bldg, Wichita, Kansas.


35-10-23E
9.2.3
card made out

RUF DRILLING CO.
H. FALK No. 7.

SEC. 35 T. 10 R. 23E.
SE SW SW NE
2090' fr E.L.
2340' fr N.L. NE $\frac{1}{4}$

Total Depth. 885
Comm. 7-14-31 Comp. 9-1-31
Shot or Treated.
Contractor. Ruf Drilling Co.
Issued. 9-10-38

County. Wyandotte.



SEP 10 1938

CASING.

65/8" 480' 47/8" 680'

Elevation. 993 (1004 Ruf US Sta)

Production. DRY.

Figures Indicate Bottom of Formations.

soil	3	limo	502	shale	765
sand rock	33	shalo	503	lime	769
lime	43	sand	513	shale	793
shale	49	King Tut gas about 50,000		lime and sand	800
lime	62	shalo	524	shale	803
shale brown	67	limo	528	red bed and white	
lime	71	shalo	530	shale	804
shale	92	limo	535	very little red bed.	
lime	107	shalo	543	shalo grey	815
shale	130	limo	544	sdv lime	818
lime	138	sdv limo hard gas		shalo white	836
shale	140	Peru filled with		plug and mud	
lime	149	mud	550	sand	842
shale	174	shalo sdv	565	Gas bubblos.	about 15,000 cu ft
lime (Iola)	207	limo	573	sdv shalo	885
shale	212	shalo blk gas and		Total Depth.	
lime	219	water	575	Dry no water in hole.	
shale	231	limo	585		
lime	241	shalo	587		
shalo	245	rod bod	590		
lime	257	shale grey	595		
shalo	274	lime SLM 600	599		
lime	276	shale	609		
shalo	278	lime plug & mud	612		
lime	280	shale	620		
shalo	286	packer set 635 for Squirrel			
lime	291	broken up sand	638	Gas bubblos	638
shalo gas	293	sand	645	Gas	184,320
lime water	314	sand	650	Gas	213,120
shalo	320	sand	664	SLM	669
lime	340	sand	680		
shalo	343	sand hard	695		
lime	344	sand	715	good oil showing- water.	
shalo	346	shale	728		
lime Hertha	359	lime	732		
shalo	373	shale	738		
sand Oil & gas sh	380	sand	745		
shalo	475	shale	756		
rod bod	476	lime	759		
sand	481	shale	760		
shalo SLM 485	500	lime	764		

(249,000 cu ft)
net. R.P.
165 lbs.
not saved