

Plotted
P.E.G.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bank Bldg, Wichita, Kansas.


18-10-24E

RUF & SONS
Loma Vista No. 11

SEC. 18 T. 10 R. 24E
SE NW SW SE
780' fr S.L. 2160' fr E.L.

County Wyandotte.

Total Depth 571
Comm. 9-6-33 Comp. 9-15-33
Shot or Treated.
Contractor.
Issued. 5-13-39



CASING.

47/8" 405'

Elevation. 898
770± ?
Production. DRY.

Figures Indicate Bottom of Formations.

soil	8	shale muddy	330
lime boulders	12	lime	331
lime	20	shale muddy	375
shale	46	shale sdy	380
lime	52	lime sdy	383
shale	59	shale	384
lime	64	red bed	388
shale	65	lime	391
lime	66	shale	395
shale	89	lime sdy	400
lime	106	shale	405
shale	110	sd lime	415
lime	115	shale	417
shale	121	lime	419
lime	125	shale	420
shale blk	126	sand hard gas in	
lime	128	top oil bot.	435
shale	136	shale	438
lime	148	lime	443
shale	154	shale blk	444
lime	167	shale	447
shale	184	lime	449
lime	187	shale SLM	457
shale	190	lime	460
lime	193	shale	464
shale	197	sand	470 Peru 98,000 G.
lime	204	shale sdy	476
shale	206	lime <i>Lex</i>	479
lime Winterset	226	shale blk	481 gas bubbles.
shale grey	228	sand	492 overall gauge
shale blk	230 wtr	lime	493 130,320 G.
gas bubbles	230	shale green, some red	
shale	233	bed	500
lime hard	250 Bothany	shale	506
shale	252 Falls	lime	507
lime	254	shale blk	508
shale	256	shale grey	516
lime	258	lime	518
shale	261 SLM 269 1/2	shale	521
lime	270	lime Ft. Scott	524
Hortha	284	shale blk	526
shale	284	shale	529 Overall gauge
sand gas bubbles	294	sd shale firm	531 98,200
shale muddy	311	sand broken wh to	
lime	317	grey	565
lime shells sdy	320	lime	567
		shale	571

Total Depth. This well was plugged
9-15-33

Squirrel