

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
 Union National Bank Bldg, Wichita, Kansas.

*J. R. ...*  
 24-10-24E  
 24


HAZLETT DECKER AND WELLS.  
 Atlas Powder Co. No. 4

SEC. ~~25~~ T. 10 R. 24E.  
 NW NE NW ~~SE~~ SE  
 1740' WEL 220' SNL

County, Wyandotte.

Total Depth. 765  
 Comm. 1-25-31 Comp. 2-4-31.  
 Shot or Treated.  
 Contractor.  
 Issued. 1-4-36.

JAN 4 1936



Elevation.

CASING.

65/8" 272'

Production. DRY

Figures Indicate Bottom of Formations.

soil	80	shale sdy	471
lime	90	lime	475
shale	101	shale blk	477
limo	115	shale	488
shale	119	lime	492
limo	130	shale and limo	499
shale	146	shale blk	503
lime	149	Gas 150,000 gas	
shale	151	lime	505
lime	154	sand	526
shale	159	oil show.	
lime	183	sand	630 wtr
shale dark	186	shale	675
Gas and water		lime	677
lime	216	shale	695
shale dark	219 wtr	lime	719
lime	223	shale sdy	765
shale	225	Total Depth.	wtr.
lime	234		
shale	348		
lime	352		
shale	371		
lime	374		
shale	380		
lime	383		
shale	412		
lime	422		
shale	430		
lime sdy	445		
lime	449		
shale dark	452		
water and gas.			
shale sdy	456		
lime	459		

Company Hazlett, Decker, Wells

Farm Atlas Powder Co. No. 4

Total Depth 765

Comm.

Shot or Treated


Contractor

Issued

Comp. 2/4/31

Sec. 25 T. 10 R. 24 E  
Loc. 1740' W of EL, 220' S of NL

County Wyandotte



Elevation 893

Production Plugged & Ab'd

Casing

20 in.	10 in.
15 1/2	8 1/4
12 1/2	6 5/8 6 1/2" --272
13 3/8	5 3/16

Figures Indicate Bottom of Formation

soil	30	lime	459
clay & boulders	50	lime & shale	471
shale blue	80	lime	475
lime grey	90	shale black	477
shale grey blue	101	shale light	488
lime	115	lime	492
shale blue	119	lime & shale	499
lime grey	130	slate black	503 150,000 gas
shale blue	146	lime & shale	508
lime	149	oil sand	526
shale dark	151	sand	630 water
lime	154	shale grey	674
shale blue	159	lime	677
lime	183	shale dark	683
shale black	186 gas & water	shale grey	685
lime	216	shale black	689
shale black	219 water	shale light	695
lime	223	lime & shale	716
shale	225	lime	719
lime	234	sand	765
shale grey sandy	257 SIM 246	water @ 730 & 740	
shale grey	310		
6 1/2" casing	272		
shale light sandy	327		
shale dark	340		
shale grey	348		
lime	352		
shale light	365		
shale green	371		
lime	374		
shale light	380		
lime	383		
shale light	412		
lime	422		
<del>shale light</del>	<del>430</del>		
shale light	430		
shale dark	445 SIM		
lime	449		
shale black	452 gas & 2BW		
shale grey sandy	456		

T.D.

*Plotted*

24-10-24E  
NW NE SW SE