

Company Newland Drilling Co.

Sec. 28 T. 10 R. 24 E *Plotted*
Loc. 140' N of SL, 1700' W of EL

Farm Gilbert

No. 1

28-10-24E

County Wvondotte

Total Depth 794


Comm. 4/3/31

Comp. 4-26-31

Shot or Treated

Contractor

Issued 10-1-38



Casing - (4 7/8" - 455')

20 in.	10 in.
15 1/2	8 1/4
12 1/2	6 5/8
13 3/8	5 3/16

Elevation 982

Production Dry & Ab'd

Figures Indicate Bottom of Formation

soil	35	sand	519
sand & gravel	42	shale, gas at 512	529
lime, water	57	lime	55
sand	60	lime	533
shale	70	shale	535
sand	75	sand	538
shale blue	88	lime	542
lime	90	shale	547
shale dark	119	lime	550
lime	145	shale	556
shale dark	174	shale light	570
lime	185	shale brown	572
shale dark	190	lime	575
lime	208	shale sandy	580
shale	212	lime	582
lime	221	shale	590
shale	238	lime	593
lime	244	shale	595
shale	250	lime	599
lime	277	shale	607
shale	282	lime sandy, gas show	615
lime	295	shale sandy	628
shale	298	sand HFW	653
shale	303	shale & lime	670
lime	310	lime sandy	677
shale	316	shale	682
red rock	319	lime	685
sand	324	shale	692
shale	331	lime	712
sand	338	shale	717
shale	443	lime	719
sand	450	shale	729
shale (set 4 7/8" pipe)	455	lime	732
lime	462	shale	742
shale	465	lime	745
lime	471	shale	758
shale	504	lime	761
lime	509	shale	766
shale	511 1/2	lime	774
		shale	794 TD