

26-10-25E  
JUN 16 1930

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location Cen WL SW NW.

Sec. 26 T.10 R.25E.

Casing Record

20" 10"  
15 1/2" 8 1/4" 101'  
12 1/2" 65/8"  
12 1/8" 53/16"  
Total Depth 371'

Farm- Fairfax No.12  
Company- Fairfax Air Port.  
Contr.-  
Comm.- 8/1/29 Shot Quarts Between  
Comp.- 8/16/29.

County- Wyandotte 1930



Correspondence Regarding This Well Should Be Referred to

Elevation Est 740'

Figures Indicate Bottom of Formations.  
Date Issued. 6/14/1930.

Initial Production  
475,000 cu. ft. Gas.

Formation	Depth
sand	96
shale	135
8" csg. at 101'	
sdv shale	150
lime	154
shale	157
red shells	160
lime & shale	165
lime	170
sand Oil Show	175
lime & shells	180
shale	190
lime	198
shale	215
sand Gas	225
sdv shale	231
lime brown	238
oil sand oil show	248
shale black	263
lime black	266
shale black gas	276
lime black	281
lime black & shells	290
shale black	300
sdv shale	330
shale black	335
shale black	347
lime black & slate	352
sand & gas	371
Total Depth	371'

*Paunce*  
*32*  
*32*

CR 26-10-25E ✓

Log from gas well, Fairfax Airports Corporation, Fairfax District,  
Kansas City, Kansas.

26 10-25  
3320 f S.L  
10 f WL

Well No. 12

<u>Thickness of strata</u>	<u>Name of rock</u>	<u>Total depth</u>	<u>Remarks</u>
96'	Sand and gravel	0 to 96'	
39'	Blue shale	96' " 135'	Set 101' 8" casing
15'	Dark sandy shale	135' " 150'	
4'	Gray lime	150' " 154'	
3'	Gray shale	154' " 157'	
3'	Red bed	157' " 160'	
5'	Lime and shale breaks	160' " 165'	
5'	Gray lime	165' " 170'	
5'	<del>Sand</del> Sand	170' " 175'	Showing of oil
5'	Lime shells	175' " 180'	
9'	Gray shale	180' " 190'	
8'	Lime	190' " 198'	
12'	Light shale	198' " 210'	
5'	Gray shale	210' " 215'	
10'	Sand	215' " 225'	Bubble of gas
6'	Gray sandy shale	225' " 231'	
7'	Brown lime	231' " 238'	
10'	Oil sand	238' " 248'	Showing of oil*
15'	Dark shale	248' " 263'	740 223 877
3'	Black lime	263' " 266'	
10'	Black shale	266' " 276'	Bubble of gas
5'	Black lime	276' " 281'	
9'	Dark lime shells	281' " 290'	
10'	Dark shale	290' " 300'	
30'	Light sandy shale	300' " 330'	
5'	Black shale	330' " 335'	
2'	Dark gray shale	335' " 347'	
5'	Black limy slate	347' " 352'	
5'	Dark gray shale	352' " 357'	
14'	Sand and gas	357' " 371'	

Comp. No. \_\_\_\_\_  
Farm \_\_\_\_\_  
NW SW NW 26 Tp. 10S R. 25E  
Well No. \_\_\_\_\_


EL. 331.0

Gauged with 2" pipe and  
gunny sacks packed in 8"  
casing showed 475,000 ft.