

Lex cap rock +465

26-10-25E

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Plotted
R.S.

Location NW cor SW.

Sec. 26 T.10 R. 25E.

Casing Record

20" 10"
15 1/4" 8 1/4"
15 1/8" 65/8"
12 1/8" 53/16"

Farm- Airport No. 13
Company- Fairfax AirPort.
Contr.-
Comm.- 9/4/29. Comp.- 9/20/29

County- Wyandotte

JUN 16 1930



Total Depth 375'. Shot Quarts Between
Correspondence Regarding This Well Should Be Referred to

Elevation Est 740'

Figures Indicate Bottom of Formations.
Date Issued. 6/14/1930.

Initial Production Dry.

2. Pawnee
1
63
1
Jok

Formation	Depth
soil & sand	94
shale	130
lime	138
shale	145
sdv shale	160
red rock	175
sand show oil & gas	190
sdv shale	212
br lime	220
shale	230
sand show oil	232
shale	247
sdv lime (Pawnee?)	253
sdv shale	259
shale	275
lime- Top 275'	279
sand gas & water	296
sand	304
sdv shale	342
shale	368
sand	375
Show oil	
T.D.	375'

MR 26-105-25E

Log from gas well, Fairfax Airports Corporation, Fairfax District, Kansas City
 Kansas.

26-10-25
 2590 FSL
 326 FWL

Well No. 13.

<u>Thickness of strata</u>	<u>Name of rock</u>	<u>Total depth</u>	
94'	River sand & gravel	0 to 94'	
36'	Blue shale	94' " 130'	
8'	Gray lime	130' " 138'	
7'	Dark shale	138' " 145'	
15'	Light sandy shale	145' " 160'	
15'	Red bed	160' " 175'	Showing of oil, little gas.
16'	Oil sand	175' " 191'	
21'	Light sandy shale	191' " 212'	
8'	Brown lime	212' " 220'	
10'	Light shale	220' " 230'	
2'	Oil sand	230' " 232'	Showing of oil
15'	Gray shale	232' " 247'	
6'	Gray sandy lime	247' " 253'	
6'	Light sandy shale	253' " 259'	
4'	Blue shale	259' " 263'	
12'	Dark shale	263' " 275'	
4'	Black lime	275' " 279'	
17'	Black shale	279' " 296'	Gas and water
8'	Sand	296' " 304'	
38'	Light sandy shale	304' " 342'	
17'	Dark gray shale	342' " 359'	
3'	Black slate	359' " 362'	
6'	Gray shale	362' " 368'	
7'	Sand	368' " 375'	Showing of oil

740#
 275
 465

County _____
 Farm _____
 sec 26 T₁₀S R 25E
 Well No. _____

368
 447
 324.3

