

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Plotted
 27-10-25E
 Plotted
 R.S.

Location NEc NW $\frac{1}{4}$


Sec. 27 T10 R25E.

Casing Record

County- Wyandotte.

JUL 28 1930

20"	10"	Farm- U.P.	No. 20
15 $\frac{1}{2}$ "	8 $\frac{1}{2}$ "	Company- Kansas City Ind. LandCo.	
12 $\frac{1}{2}$ "	65/8"	Contr.-	
	53/16"	Comm.- 9-4-29	Comp.- 9-15-29
Total Depth 368		Shot	Quarts Between



Figures Indicate Bottom of Formations.
 Date Issued. 7/26/1930

Elevation Est 741
 Initial Production 1,175,000 G.

Formation	Depth.
sdv soil	15
river sand and gravel	96
shale dark	100
sand grey	120
shale dark	130
sand grey.	145
red rock	155
limey shale	170 170 4/7/8 csg.
lime grey	176
greys and showing oil	190
lime grey	197
sdv shale dark	207
sand grey gas	212
sdv shale light	217
shale dark grey	224
lime brown	230
shale light	235
sand little gas	250
shale dark	261
lime blk	265
slate limey	285
shale dark	290
sand grey	300
sdv shale light	315
shale grey	320
limey slate	329
shale light	333
slate and lime blk	347
sand gas	368
Total Depth.	
showing of blue shale 68'	
set packer 313	
set cave packer 338.	
top gas gauges 106,000	
bottom " 1,009,000	
Total 1,175,000	

Packer
 37'
set

Log From Gas Well, The Kansas City Industrial Land Company,
Fairfax Industrial District, Kansas City, Kansas.

at R
27-10-25E
5140 f.s.l
2700 "E"

Well No. 20.

<u>Thickness of strata</u>	<u>Name of Rock</u>	
15'	Sandy soil	0' to 015'
81'	River sand & gravel	15' " 096'
4'	Dark shale	96' " 100'
20'	Gray sand	100' " 120'
10'	Dark shale	120' " 130'
15'	Gray sand	130' " 145'
10'	Red rock	145' " 155'
15'	Limey shale	155' " 170'
6'	Gray lime	170' " 176'
14'	Gray sand, showing oil	176' " 190'
7'	Gray lime	190' " 197'
10'	Dark sandy shale	197' " 207'
5'	Gray sand, gas	207' " 212'
5'	Light sandy shale	212' " 217'
7'	Dark gray shale	217' " 224'
6'	Brown lime	224' " 230'
5'	Light shale	230' " 235'
15'	Sand, little gas	235' " 250'
11'	Dark shale	250' " 261'
4'	Black lime	261' " 265'
20'	Limey slate	265' " 285'
5'	Dark shale	285' " 290'
10'	Gray sand	290' " 300'
15'	Light sandy shale	300' " 315'
5'	Gray shale	315' " 320'
9'	Limey slate	320' " 329'
4'	Light shale	329' " 333'
14'	Black slate & Lime	333' " 347'
21'	Sand gas	347' " 368'

Set 170' 4-7/8" csng.

741
261
486

Company
Farm
Sec. 27 Tp. 10S R. 25E
Map No. Well No. 20

Showing of blue shale at 68'
Set packer at 313'
Set cave packer at 338'

Elevation top of ground 327.7
Top gas gauges 106,000
Bottom " " 1,069,000
Total 1,175,000 cu ft.

741.2 elev