

Plotted
28-10-25E

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY


UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location SE SE NE NE

Sec. 28 T. 10 R. 25E.

Casing Record

20"	10"	Farm-	U.P.	County-	Wyandotte
15"	8 1/4"	123	Company-	Kansas City Ind. Land Co.	No. 24
12 1/2"	65/8"	185	Contr.-		
	53/16"		Comm.-	11-18-29	Comp.-12-4-29
Total Depth	115		Shot	Quarts Between	



Elevation Est 745'

Figures Indicate Bottom of Formations.

Initial Production 5 bbls.

Date Issued. 8/9/1930

Formation	Depth.
surface sand	12
fine river sand	65
coarse river sand	107
sandstone grey	140
shale dark	150
shale green	160
shale light	173
lime grey	180
shale light	190
shale green	200
shale grey	207
lime grey	212
shale limey grey	230
almost hard shale	234
lime brown	243
sand soft	246 little gas
sd shale light	255
shale dark	265
lime blk hard	269
shale blk	272 some gas.
lime dark	274
sd shale blue	281
oil sandhard	293
shale blue	300
lime dark hard	304
limey shale dark	307
lime grey	310
sd shale	320
sand soft	332
332 4 7/8 casing.	
shale blue	349
limey shale dark	362
shale blue	367
shale blk	371
shale grey	378
reduced to 4-7/8	372
sand grey	397
sd shale blue	403
sand grey	409
sand blue	415
Total Depth.	
set packer 277 feet.,	

Panner

31

set

