

25-29-5E

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - COOPERATIVE REFINERY ASSOCIATION
Farm - Warner No. 18

SEC. 25 T. 29 R. 5E
CW/2 SW NE

Total Depth. 2798 PB 2783'
Comm. 3-23-49 Comp. 5-9-49
Shot or Treated. Shot w/40 qt. 2767-81
Contractor. Shawver-Graham
Issued. 7-16-49

County. Butler

KANSAS



Elevation. 1318 ind

CASING:

10" 92' cem. w/50 sx
7" 2763' cem.w/90 sx

Production. Dry

Figures Indicate Bottom of Formations.

surface hole	92
lime	125
lime, shale	545
red rock	550
lime, shale	2128
lime	2352
shale, lime	2468
shale, shells	2515
lime	2525
shale	2540
lime, shale	2610
shale	2650
shale, lime	2726
shale	2740
sand	2745
core (Rotary)	2778
core (Electrodrill)	2798
Total Depth	
PB 2783'	

TOPS:

Kansas City	2122
Bartlesville	2761
Base Bartlesville	2797

Good stain & porosity in top
5' of Kansas City 2122-27
Core #1: 2743-60 (recovered 17')
Gray shaly sand
Core #2 2760-78 (recovered 18')
Gray sand w/few shaly streaks
Well stained 2761-71
Core #3 2778-98 (recovered 20')
Gray shaly sand
Temporarily abandoned 5-9-49