

Copied from old log book in E. A. Cullum estate
No other information FCG 10/4/43

cc: fog.

27-F-30

MISSOURI GEOLOGICAL SURVEY AND WATER RESOURCES - ROLLA, MO.

COUNTY Wyandotte, Kansas LOG NUMBER _____

COMPANY OR OWNER _____

FARM _____ WELL NO. _____

LOCATION _____ SEC. 33 T. 10S R. 25E

CONTRACTOR _____

DRILLER _____ TOOL DR. _____

COMMENCED _____ COMPLETED _____

PRODUCTION _____ PLOTTED _____

CASING RECORD _____

WATER RECORD _____

SOURCE OF LOG Drillers originalREMARKS "Ninth & Quindaro" Kansas City, Kansas

ELEV. _____

TOTAL DEPTH 380

CHEM. ANAL. NO. _____

FORMATION	THICK.	DEPTH	FORMATION	THICK.	DEPTH
Sandy clay	42	42	Sand	7	332
Quicksand	11	53	Light shale	3	335
Blue sandy muddy shale	24	77	Blue shale	4	339
Lime boulders	3	80	Black slate gas bubbles	2	341
(reduced hole at 59 ft. set 50 ft. of 6 1/4 casing)			Brown lime	5	346
Lime	23	103	Gas sand	4	350
Dark shale	5	108	Water sand	2	352
Dark gray lime	21	129	Dark shale SLM 365	13	365
Dark shale	3	132	packer 366		
Lime	3	135	Black lime	3	368
Blue shale	2	137	Dark shale	4	372
Lime (little water)	8	145	Gas sand	6	373
Green shale (little water)	4	149	Blue shale	2	380
Green sandy shale	11	160			
Blue sandy shale	85	245			
Light shale	22	267			
Dark shale	7	274			
Coarse dry sand	8	282			
Light shale	4	286			
Coarse dry sand	5	291			
Light sandy shale	7	298			
Red bed	2	300			
Green shale	14	314			
Gray ~~sh~~ lime	6	320			
oil showing gas bubble					
Sand	5	325			

Bottom hole 380 SLM

(#) all in same band and same look

30-105-25E

27-F-30

MISSOURI GEOLOGICAL SURVEY AND WATER RESOURCES - ROLLA, MO.

COUNTY Wapanda LOG NUMBER _____

COMPANY OR OWNER _____

FARM _____ WELL NO. _____

LOCATION _____ SEC. 30 T. 10S R. 25E

CONTRACTOR _____

DRILLER _____ TOOL DR. _____

COMENCED _____ COMPLETED _____

PRODUCTION _____ PLOTTED _____

CASING RECORD _____

WATER RECORD

SOURCE OF LOG E A Miller long work

REMARKS ninth and Quindaro

ELEV. _____

TOTAL DEPTH 380

CHEM. ANAL. NO. _____

up to 10/10/13

FORMATION	THICK.	DEPTH	FORMATION	THICK.	DEPTH
Sandy clay	42	0	Green sand		
Crack sand	11	42	Shale	11	149
Blue sandy sandy			Blue sandy		
Shale	24	53	Shale	85	160
Large boulders	3	77	Light shale	22	245
Reduced hole at 59ft			Dark shale	7	267
76% down 30ft			Coarse clay		
6% clay			Sand	8	274
2 mi	23	80	Light shale	4	282
Dark shale	5	103	Coarse clay		
Dark grey lim	21	108	Sand	5	286
Dark shale	3	129	Light sandy		
Lim	3	132	Shale	7	291
Blue shale	2	135	Red Mud	2	298
Lim	8	137	Green shale	14	300
with water			Gray lim	6	314
Green shale	4	145			
with water					

30-105-25E

Sand	5	320	325	oil showing
Sand	7	325	332	gas bubble
Light shal	x4	332	335	
Blue shal	4	335	339	
Black slate	2	337	341	gas bubbles
Brown lin	5	341	346	
Gas sand	4	346	350	
Water sand	2	350	352	
Dark shal	13	352	365	SLM 365
Black lim	3	365	368	Fraser 366
Dark shal	4	368	372	
Gas sand	6	372	378	
Blue shal		378	380	
Bottom hole 380 SLM				

Wyanotte Co
 Sec 30 T10S R 25E
 Ninth and Quindaro St
 K.C. Ks