

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


6-32-5E

Company- MORRISON PRODUCING CO.
Farm- Elrod "B" No. 3

SEC. 6 T. 32 R. 5E
NW SW NE

Total Depth. 3100'
Comm. 9-23-57 Comp. 10-1-57
Shot or Treated.
Contractor. Glen Drlg., Inc.
Issued. 6-7-58

County Cowley
KANSAS



CASING:
8 5/8" 150' surf. com
5" 2600'

Elevation. 1258' RB

Production. 10 BOPD

Figures indicate Bottom of Formations.

sod	5
lime	85
shale	90
lime	110
red rock	120
lime brkn	155
lime	525
lime, shale	610
shale, lime stks	850
lime	895
shale, lime	1010
shale, shells	1320
shale, lime	1550
shale, shells	1650
lime, shale	1669
shale, sand	1787
sand, shale	1912
sand	2012
sdv shale	2095
sand	2124
shale, shells	2283
shale	2315
Diamond Core	2355
shale, sand	2415
lime	2462
lime	2525
shale, lime	2546
lime	2592
shale, lime stks	2624
shale, shells	2650
lime	2700
lime, shells	2738
lime	2820
shale, lime stks	2894
sand, lime stks	2908
Diamond Core #2	2941
shale, sand stks	2986
sand	3012
sand, shale	3050
lime, Mississippi	3100
Total Depth	

TOPS: Scout	
Layton	2325
Kansas City	2440
Cherokee	2805
Cattlemen Zone	2892
Mississippi	3055