

DRILLING REPORT NO. 1

TO Mid-Continent Petroleum Corporation Dec. 11, 19 36

Scouting Department
Cosden Building Box 381

Tulsa, Oklahoma

STATE OF Kansas

BLOCK Wiesner

LOCATION OF WELL: SEC. 12 TWP. 14 S RGE. 19 W

ELEVATION 2181'

DRILLING CONTRACTOR R. R. Grandin

COUNTY OF

NAME OF LESSOR A. A. Wiesner

Ellis

NAME OF LESSEE Murphy Oil Co. of Pa.

CASING RECORD

NAME OF OPERATOR Murphy Oil Co. of Pa., M. R. Brann

B. B. Blair

15 1/2" set 798'

LOG OF WELL

Gellar	0	12	blue shale	720	775
yellow clay	12	55	light clay	775	780
blue gumbo	55	75	white shale	780	795
blue slate	75	175	lime	795	805
shale dark	175	215	white slate	805	810
blue shale	215	270	blue shale	810	820
Light show gas 255'			white shale	820	830
shale light	270	455	blue shale	830	832
shell	455	460	pyrites	832	835
soft light shale	460	500	white shale	835	845
shale pink & red	500	535	light shale	845	855
shale light	535	540	grey shale	855	880
red rock	540	555	red rock	880	885
blue shale	555	560	sand	885	890
red shale	560	565	red sand	890	920
red rock	565	590	red bed	920	930
light shale	590	596	sand	930	935
red bed	596	598	red rock	935	940
shell	598	600	blue shale	930	955
red rock	600	630	sand	955	985
sand-water	630	645	red sand	985	1015
blue shale	645	650			
light shale	650	660			
sand-water HFW	660	670			
sand	670	705			
blue slate	705	720			

To December 8, 1936

BY _____

DRILLING REPORT

TO Mid-Continent Pet. Corp January 25 19 37

Scouting Dept. Box 381

Tulsa, Oklahoma

STATE OF Kansas

BLOCK Weisner

LOCATION OF WELL: SEC. 12 TWP. 14 S RGE. 19 W

ELEVATION 2181½

DRILLING CONTRACTOR R. R. Grandin

COUNTY OF

NAME OF LESSOR A. A. Weisner

Ellis

NAME OF LESSEE Murphy Oil Co. of Pa.

CASING RECORD

NAME OF OPERATOR Murphy Oil Co., M. R. Brann
E. B. Blair

12½" set 1448'

LOG OF WELL

(Continuation)

red sand	1015	1100	salt	2070	2095
red rock	1100	1135	grey shale	2095	2105
blue shale	1135	1140	lime	2105	2110
red rock	1140	1203	grey shale	2110	2120
iron pyrites	1203	1205	lt shale & shells	2120	2140
red rock	1205	1305	white lime	2140	2145
red shale	1305	1340			
red rock	1340	1440			
anhydrite	1440	1490			
red rock	1490	1625			
blue shale	1625	1650			
red rock	1650	1715			
blue shale	1715	1720			
red rock	1720	1740			
grey shale	1740	1750			
red rock	1750	1760			
blue shale	1760	1830			
broken lime	1830	1850			
red rock broken	1850	1860			
salt	1860	1940			
grey shale	1940	1950			
salt	1950	2020			
grey shale	2020	2035			
salt	2035	2050			
lime shale	2050	2056			
blue shale	2056	2070			

Including Jan. 22, 1937

DRILLING REPORT

TO Mid-Continent Petroleum Co., Feb. 19, 19 37
Scouting Dept. Box 381
Tulsa, Oklahoma STATE OF Kansas

BLOCK Weisner

LOCATION OF WELL: SEC. 12 TWP. 14S RGE. 19 W

ELEVATION 2181'

DRILLING CONTRACTOR R. R. Grandin COUNTY OF

NAME OF LESSOR A. A. Weisner Ellis

NAME OF LESSEE Murphy Oil Co. of Pa.

CASING RECORD

NAME OF OPERATOR Murphy Oil Co., M. R. Erann
B. E. Bialk

10" set 2690'

LOG OF WELL

(Continuation)

lime	2525	2555
red rock	2555	2570
lime	2570	2600
light shale	2600	2625
sand	2625	2630
sandy lime	2630	2645
red rock	2645	2667
white lime	2667	2670
lime soft	2670	2675
lime hard grey	2675	2698
shale blue	2698	2700
white lime hard	2700	2712
shale	2712	2715
red rock	2715	2725
gritty lime	2725	2740
lime	2740	2755
sandy shale	2755	2760
brown shale	2760	2765
brown broken lime	2765	2810
lime solid	2810	2825

Including February 15, 1937

DRILLING REPORT

TO Mid-Continent Petroleum Corp., Mar. 12 19 37

Cosden Bldg.,

Tulsa, Oklahoma

STATE OF Kansas

BLOCK Weisner

LOCATION OF WELL: SEC. 12 TWP. 14 S RGE. 19 W

ELEVATION 2181'

DRILLING CONTRACTOR R. R. Grandin COUNTY OF Ellis

NAME OF LESSOR Murphy A. A. Weisner

CASING RECORD

NAME OF LESSEE Murphy Oil Co. of Pa.

8 1/4" set 3185'

NAME OF OPERATOR Murphy Oil Co., M. R. Brann, B. B. Blair

LOG OF WELL

(Continuation)

blue shale	2825	2835
lime	2835	2838
blue shale	2838	2845
lime	2845	2850
grey shale	2850	2868
lime	2868	2877
blue shale	2877	2885
light shale	2885	2890
shale blue	2890	2900
lime	2900	2915
blue shale	2915	2925
grey shale & shells	2925	2950
lime hard	2950	2953
light blue shale	2953	3000
shale grey	3000	3010
lime	3010	3025
blue shale	3025	3060
grey shale & shells	3060	3080
lime	3080	3085
grey shale	3085	3090
lime	3090	3100
blue shale	3100	3125
grey shale	3125	3165
shell	3165	3167
grey shale	3167	3170
sandy shell	3170	3175
lime	3175	3181
lime	3181	3230
shale blue	3230	3235
lime	3235	3260

Including March 9, 1937

DRILLING REPORT

TO Mid-Continent Pet. Corp., Feb. 6, 19 37

Scouting Dept. Box 381

Tulsa, Oklahoma

STATE OF Kansas

BLOCK Weisner

LOCATION OF WELL: SEC. 12 TWP. 14 S RGE. 19 W

ELEVATION 2181'

DRILLING CONTRACTOR R. R. Grandin

COUNTY OF _____

NAME OF LESSOR A. A. Weisner

Ellis

NAME OF LESSEE Murphy Oil Co. of Pa.,

CASING RECORD

NAME OF OPERATOR Murphy Oil Co., M. R. Brann

10" set at 2426'

B. B. Blair
LOG OF WELL

(Continuation)

lime	2145	2150
grey shale	2150	2155
lime	2155	2160
grey shale	2160	2170
red rock	2170	2200
broken lime	2200	2230
sandy lime	2230	2235
brown shale	2235	2270
lime	2270	2275
grey shale	2275	2285
brown shale	2285	2305
broken lime	2305	2315
lime	2315	2335
brown shale	2335	2345
lime	2345	2355
shale light	2355	2405
red & white		
broken lime	2405	2420
red rock	2420	2443
broken lime	2443	2465
light shale	2465	2470
brown shale	2470	2473
lime hard	2473	2500
grey shale	2500	2505
red rock	2505	2520
lime white	2520	2525

Including Feb. 3

DRILLING REPORT

TO Mid-Continent Pet. Co.,
Scouting Dept. Box 381
Tulsa, Oklahoma

April 21 19 37

STATE OF Kansas
 COUNTY OF Ellis

BLOCK Weisner

LOCATION OF WELL: SEC. 12 TWP. 14S RGE. 69W

ELEVATION 2191'

DRILLING CONTRACTOR R. R. Grandin

CASING RECORD

NAME OF LESSOR A. A. Weisner

NAME OF LESSEE Murphy Oil Co. of Pa.

NAME OF OPERATOR Murphy Oil Co., Mr E. Brann
E. E. Blair

LOG OF WELL

lime	3260	3275
sandy lime	3275	3295
lime	3295	3440
blue shale	3440	3445
shale light	3445	3460
lime	3460	3475
red rock	3475	3480
lime	3480	3490
light shale	3490	3500
lime	3500	