


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- AYLWARD DRILG. CO. ET AL
Farm- Hallman No. 2

SEC. 23 T. 34 R.3E
NW SW NE

Total Depth. 3389
Comm. 6-21-54 Comp. 6-29-54
Shot or Treated.
Contractor. Aylward Drilg. Co.
Issued. 9-18-54

County Gowley
KANSAS



Elevation. 1170 DF

Production. Pmp. 30 BO & VSSW

CASING:

8 5/8" 951
5 1/2" 3375' cem. w/ 50 sx

Figures indicate Bottom of Formations.

sand	30
sand & clay	95
shale & sholls	535
sdv shale & lime	543
sdv lime & shale	669
shale & lime	934
shale & sholls	1225
shale & lime	1540
shale & sholls	1700
sdv lime & shale	1926
shale & sholls	2074
shale & lime	2673
sand & shale	2805
sdv shale	2870
lime	2895
lime & shale	3073
lime	3137
lime & shale	3368
sand	3379 RTD

Cable Tool Information:

Cleaning out DD 3384 (Sand)
Show of oil-Sand frac; Swab
208 BO 9 hrs.; DD 3386 (Shale)
DD 3389 TD; POP
Total depth

Tops:

Kansas City sand	2867
Kansas City lime	2884
Oswego lime	3059
Cherokee shale	3169
Bartlesville zone	3343
Bartlesville sand	3368
Rotary TD	3379