


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CREST PETROLEUM, INC AND N.C.R.A.
 Farm- Jones Estate No. 3

SEC. 28 T. 34 R. 3E
 NW SW NW

Total Depth. 3401
 Comm. 6-22-54 Comp. 7-2-54
 Shot or Treated.
 Contractor. Fortier & Wright Drilg. Co.
 Issued. 9-4-54

County Cowley KANSAS



CASING:

8 5/8" 90' cem. w/100 sx
 5 1/2" 3401' cem. w/75 sx

Elevation. 1132 KB

Production. Est. 30 BOPD & 60 BW

Figures Indicate Bottom of Formations.

sub-soil	30
lime	35
sand & shale	75
lime	90
lime, rodbed & shale	420
lime & shale	595
sdv lime & shale	935
sand, lime & shale	1235
shale & lime	1875
sha le	1955
lime & shale	2195
sand & shale	2320
lime, sand & shale	2435
shalc	2666
Layton sand	2790
shale	2895
shale & lime	2960
lime, sand & sha le	3065
lime & shale	3295
shale	3356
Bartlesville sand	3388
Miss. lime	3401
Total depth	

Tops:

Stalnaker sand	2208
Layton sand	2656
Kansas City	2868
Cleveland Zone	2978
Big Lime	3062
Oswego lime	3098
Bartlesville sand	3356
Mississippian	3388

Core No. 1 - 3358-3391, Rec. 33 feet
 3358-3388 sand
 3388-3401 cherty lime

Perforated: w/94 holes 3366-3384
 fractures; Est. 30 BOPD and 60 BW