


Company- ALADDIN PETRO. CORP.  
 Farm- Baird No. 9

SEC. 29 T. 34 R. 3E  
 NE SE NE

Total Depth. 3895'  
 Comm. 9-10-54 Comp. 10-21-54  
 Shot or Treated.  
 Contractor. Tri State Drlg. Co.  
 Issued. 11-13-54

County Cowley  
 KANSAS



Elevation. 1140' DF

CASING:  
 8 5/8" 134' w/125 sx cem.  
 5 1/2" 3800' w/150 sx cem.

Production. 290 B/dry after  
 fracturing

Figures Indicate Bottom of Formations.

soil-shale	35
shale-shells	50
sand wtr	56
lime	200
red rock	210
shale-lime	350
red rock	365
lime	525
lime	585
red bed-shale	675
limo-shale	725
shale-shells	1150
shale-lime	1275
shale-lime shells	1435
shale-shells	1540
limo-shale	2648
sand Layton	2730
sand	2767
shale	2875
lime-shale	2980
sd shale	3025
shale	3060
lime	3165
shale-lime	3338
shale	3352
coring	3356
coring	3389
lime Mississippi	3395
Mississippi chat	3405
lime	3515
lime-shale	3626
lime	3628
shale-lime	3711
shale	3720
red-shale	3724
?	3726
coring	3726-3740
coring	3740-3759
reared core hole	3627-3759
Core #2	3766
shale-sdy	3776
sand-shale	3782
shale-lime	3804
lime	3895
Total Depth	

---

TOPS: Scout	
Kansas City	2864
Cleveland	2979
Marmaton	3051
Cherokee	3169
Bartlesville	3359
Mississippi	3393
Simpson	3721
Simpson sand	3761
Arbuckle	3893