


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MCNEISH & GRALAPP ET AL
Farm- Wilson "A" No. 4

SEC. 29 T. 34 R. 3E
SE NE SW

Total Depth. 3400
Comm. 9-16-52 Comp. 10 -8 -52
Shot or Treated.
Contractor. Watson Drlg. Co., Inc.
Issued. 2-21-53

County Cowley
KANSAS



CASING:

8 5/8" 107' cem. w/100 sx
5 1/2" 3387' cem. w/100 sx

Elevation. 1119
Production. 88 BO & NT
1151 (Ind)

Figures indicate Bottom of Formations.

sand	49
shale	66
lime	107
lime & shale	220
red rock	235
lime & shale	390
red rock	405
lime	600
shale	900
shale & lime shells	1180
lime & shale	1370
shale, sand, red rock	1510
shale & lime	1540
lime	1710
shale & lime	2135
sandy shale & lime	2220
lime	2230
sand & shale, hrd	2280
sand & shale	2350
sandy lime & shale	2478
shale & lime	2543
lime & shale	2573
shale	2684
sand & shale	2691
sand	2768
shale & lime	2788
sand & shale	2825
shale	2877
lime K.C. & shale	2889
lime	2890
sand, shale & lime	2933
lime brown	2950
lime	2970
lime & shale	3125
lime	3190
lime & shale	3370
core 3370	3396
core 3396	3400
sand	3400 RTD
Total Depth	

Scout Tops:
Stalnaker 2230
Bart. Sand 3370

10-1-52 Dumped Cal Seal & hydrafracing
Cable Tool - Did not Drill deeper.