


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MC NEISH & GRALAPP
 Farm- Simeon No. 1

SEC. 31 T. 34 R. 3E
 NW SW NW

Total Depth. 3520
 Comm. 12-21-54 Comp. 1-15-55
 Shot or Treated.
 Contractor. Watson Drlg Co., Inc.; M.G.M.
 Issued. 2-12-55

County Cowley
 KANSAS



CASING:

8 5/8" 97'
 5 1/2" 3525.2" cem w/75 sx

Elevation. 1210 R.B.

Production. 25 bbls

Figures indicate Bottom of Formations.

surface soil	120
lime	162
lime, shale	320
red bed	335
lime, shale	2055
lime, sdy shale	2100
shale sdy	2200
shale, sand strks	2373
sand	2467
shale, hard sand	2564
shale sdy	2653
shale, sand	2755
shale	2771
sand, shale strks	2798
sand	2872
shale sandy	2948
shale	2971
lime, Kansas City	3142
lime, shale	3174
lime	3315
lime, shale	3350
shale, lime shells	3370
shale, lime	3430
shale sdy	3463
sand find, shale	3474
sand	3520
Total Depth	RTD

Tops: Scout.
 Kansas City 2982
 Bartlesville 3475

Perf. 3493-3503 74 shots
 Perf. 3474-3486 48 shots
 Fractured 1-14-55