


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- ALADDIN PETROLEUM CORPORATION
Farm- Baird-Dronnan No. 12

SEC. 32 T. 34 R. 3E
NW SE NE

Total Depth. 3790 Rot. Meas.
Comm. 3-5-54 Comp. 3-25-54
Shot or Treated.
Contractor. Crowe Drilg. Co., Inc.
Issued. 6-19-54

County Cowley KANSAS



CASING:
8 5/8" 135' cem. w/125 sx
5 1/2" 3784' cem. w/150 sx

Elevation. 1139 GM

Production. 3000 Bbls. oil

Figures indicate Bottom of Formations.

top soil & clay	60
lime, shells & shale	120
lime	135
lime & shale	375
redbed	400
lime & shale	635
redbed	705
shale & shells	1142
sand & shale	1152
shale & shells	1695
shale & lime	2225
Stalnaker sand	2370
shale & lime	2680
Layton sand	2792
shale & sand	2841
shale & lime	2985
lime, shale & sand	3046
lime	3050
lime & shale	3414
Miss. Conglomerate	3442
Miss. lime	3560
lime & shale	3585
Miss. lime	3670
shale	3715
shale sandy	3786
Simpson dolomite	3790
Total depth Rotary Meas.	
(G.M. Total depth 3784)	

Deduct 2' from above to equal
Derrick Floor Measure

Tops:Scout	
Bartlesville	3357
Mississippi chat	3418
Mississippi lime	3440
Simpson	3710
Arbuckle	3784