


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- THE TEXAS COMPANY  
Farm- L. M. Bryant No. "B" 4

SEC. 32 T. 34 R. 3E  
NE NW SW

Total Depth. 3408'  
Comm. 12-28-52 Comp. 1-21-53  
Shot or Treated.  
Contractor. Capitt Drlg. Co.  
Issued. 3-14-53

County Cowley  
KANSAS



CASING:  
10 3/4" 110' cem w/150 sx.  
7" 3397' cem w/200 sx.

Elevation. 1145 DF  
1147 (Ind)  
Production. Pumping 51 BBls.  
and 10 Bbls.

Figures Indicate Bottom of Formations.

surface clay	25
shale	60
lime, shale	110
red rock	250
lime, shale, shells	545
red rock	620
shale, lime red rock	1260
lime, shale	1300
shale, shells	1315
shale, lime red rock	1395
lime, shale	1415
shale, shells, red rock	1455
sand, shale	1505
shale, lime, red rock	1665
shale, shells	1799
shale, lime red rock	1818
sand, shale, red rock	2130
shale, sandy limo shells	2215
shale, shells	2275
sand, shale	2380
shale, lime, red rock	2480
shale, red rock, lime shells	2590
shale, shells, red rock	2682
sand Layton	2730
sand	2770
sand, shale	2886
lime, shale	2954
shale, red rock	3105
lime, shale	3155
shale, lime red rock	3398
sand	3408
Total Depth	
Tops-Scout	
Topeka	1538
lotan	2211
Stalnaker	2237
Layton	2679
Kansas City	2874
Marmaton	3078
Cherokee	3204
Bartlesville Sec.	3347
Bartlesville sand	3379

Measurement from BH-KB 5.6', Bh-GL .5'