

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


1 - 30 - 5E

Company- STELBAR OIL CORPORATION, INC.
 Farm- Brown Unit No. 6

SEC. 1 T. 30 R. 5E
 SWc SE NE

Total Depth. 2820 PBTD 2815
 Comm. 11-1-55 Comp. 11-7-55
 Shot or Treated.
 Contractor. Stelbar Oil Corporation, Inc.
 Issued. 2-4-56

County Cowley
 KANSAS



CASING:
 8 5/8 128' w/ 80 sx cmt.
 5 1/2 2777' w/ 80 sx cmt.

Elevation. 1322 DF

Production. 50 BOPD

Figures indicate Bottom of Formations.

broken lime	44
lime	176
broken lime	300
shale & shells	2158
K. G. lime	2380
shale & lime	2776
Bartlesville-cored	2780
sand-cored	2816
shale-cored	2820
Total Depth	

Plugged back to 2815

TOPS:
 Kansas City 2155
 Bartlesville 2759

RB Meas.

Dumped 250 gal MCA DC.
 Cored 2780-2820
 sand 2776-2816

Fracked w/ 5000 GO, 12000# sand,
 BDP 750 to 400# TP 750 to 400#
 FP 300#