

WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY
UNION NATIONAL BANK BLDG., WICHITA, KANSAS

CASING RECORD

LOCATION

NW cor SW/4 SE/4

SEC 21 T 28 R 4 E.

10" 780 FARM Wm. & Frank Bloss NO. 1 COUNTY Butler

20" 8 1-4 1765 COMPANY Mid-Kansas Oil & Gas Co.

15 1-2 6 5-8 2282 CONTRACTOR Sidwell Brothers.

12 1-2 86 5 3-16 COMMENCED COMPLETED

TOTAL DEPTH 2625'. SHOT QUARTS BETWEEN


CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO Mid-Kansas Oil & Gas

Co., El Dorado, Kansas. ELEVATION

FIGURES INDICATE BOTTOM OF FORMATIONS.

REMARKS 5/14/27

INITIAL PRODUCTION



Formation	Depth
soil	5
slate	30
gravel	35
slate	43
lime shell & slate (Water 60')	120
lime	130
slate	140
red rock	155
lime	165
slate	190
lime	200
slate	230
lime	240
slate	270
lime	280
slate (6 B. W. 300')	290
lime	330
slate	335
lime	365
slate	455
lime	500
mud blue	515
slate	600
lime	730
slate	860
lime	875
slate	895
lime	900
slate	955
lime	1270
slate	1320
lime (First gas 1418')	1355
slate (Gas at 1442')	1410
lime	1550
slate & lime (Gas at 1458')	1743
slate	1765
lime	1860
slate	2010
slate	2110
lime	2205
slate	2270
lime	2352
slate	2523
red rock	2570
slate	2620
sand	2625

H. F. W.