

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY:
412 Union National Bank Bldg, Wichita, Kansas.


Plotted *Apr*

RYAN CONSOLIDATED PETRO. CORP.
Marble Savings Bank No. 1.

13-30-5E
SEC. 13 T. 30 R. 5E.
NEcNW

Total Depth. 2839
Comm. 9-11-40 Comp. 9-21-40
Shot or Treated.
Contractor. Big West Drilling Co.
Issued. 12-7-40

County Cowley.



CASING.

1 3/8 " 95'
7" 2786'

Elevation.

Production! Pot! 520 B.

Figures Indicate Bottom of Formations:

..

surface soil	40
broken line	380
shale and shells	1060
shale	1140
lime	1440
lime and shale	1690
lime	1765
shale and sand	1822
shale and shells	1902
lime	1948
shale and lime	2050
lime	2065
shale and lime	2535
lime	2681
shale and shells	2790
shale	2803
sand	2808
core - sand shale	2837
sand	2839
Total Depth.	

S

Oil sand 2805-2839