

# WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY

719-20 Union Nat'l Bank Bldg: Wichita, Kansas.

CASING RECORD


LOCATION NE  $\frac{1}{4}$  NW  $\frac{1}{4}$

SEC 32 T 30 R 5 E.

10"  
20" 8 1-4  
15 1-2 6 5-8  
12 1-2 5 3-16

FARM Withers  
COMPANY Pettit & Benks.  
CONTRACTOR  
COMMENCED

NO. 1 COUNTY Cowley



TOTAL DEPTH SHOT QUARTS BETWEEN  
CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO

ELEVATION 1298  
INITIAL PRODUCTION (D. & A.)

FIGURES INDICATE BOTTOM OF FORMATIONS.  
REMARKS

Formation	Depth	Formation	Depth	Formation	Depth
surface					
lime	105	shale	740	shale, blue	1555
slate	140	lime	780	red mud (cave)	1575
lime	145	shale	880	blue mud (cave)	1650
shale	155	lime	897	blue shale	1895
red rock	170	shale black	905	sand, water	1940
lime	190	lime	920	shale	2020
shale	205	shale, blue	960	lime	2046
lime	230	lime	965	shale, sandy	2075
lime	260	shale, blue	1020	sand, HF water-	2085
shale	285	lime	1200	shale, blue	2160
lime	310	black mud	1205	shale, black	2165
sand, water	325	shelly	1230	shale, blue	2234
lime white	335	lime	1270	lime, white	2275
shale	345	shale, blue	1235	lime, black	2290
lime	360	lime	1300	lime, white	2348
slate	400	shelly	1307	sand, water HF	2365
shale blue	410	lime	1315	sand, dark	2370
lime hard	425	lime	1350	lime, black & white,	
lime hard	450	shale, black	1365	hard	2485
slate	460	lime, white	1385	(1 B. water)	
lime	520	shale, white	1415	shale, black	2540
sand water	540	lime, dark	1423	lime	2560
lime	590	shale, white	1430	shale	2630
shale	610	sand, white	1435	lime	2665
lime	640	lime	1445	shale, black	2670
shale	710	sand, water HF	1450	lime	2680
lime	740	sandy lime	1475	shale, black	2840
		shale, blue	1515	shale, white	2860
		lime	1520	sand, show of oil	
				1 ft	2861
				shale, black	2900
				chat	2918
				lime, hard, Miss.	2921