

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - THE SACO OIL COMPANY
Farm - Covert "A" No. 1

SEC. 10 T. 28 R. 5E
NE. SW. NW

Total Depth. 3183'
Comm. 6-7-47. Comp. 7-13-47
Shot or Treated.
Contractor. THE SACO OIL COMPANY
Issued. 10-4-47

County. Butler

KANSAS



Elevation. 273 *set 4/11*

Production. DRY & ABANDONED

CASING:

20" @ 28'
15 1/2" @ 385'
12 1/2" @ 1006'
10" @ 1640'
8 1/2" @ 2285'
7" @ 2745'

Figures Indicate Bottom of Formations.

cellar	8	lime	950	shale	2545
red clay	25	shale	1004	lime	2550
gravel	55	lime	1050	shale	2570
shale	80	shale	1120	shale & shells	2630
lime	95	lime shells	1135	shale	2665
shale	105	lime	1165	lime	2670
lime	110	shale	1180	shale red	2675
shale light	140	lime	1215	shale	2710
shale blue	145	shale	1230	sand broken	2719
red rock	155	lime	1240	MEAS. CORR.	2729
shale sandy	160	shale & shells	1255		
shale	170	lime	1270	lime Base	3056
lime	180	shale	1275	shale black	3095
shale	195	lime	1345	shale	3142
lime	205	shale-black	1350	sand	3157
shale	280	shale	1355	green shale	3168
lime	290	lime	1400	sand-hard & sharp	3177
shale	320	shale	1455		
lime	340	lime	1505	lime	3183
shale	345	shale	1515	Total Depth	3183
lime	355	lime	1535		
shale	385	shale	1535		
lime	435	shale	1605		
shale	450	sand	1620		
lime	460	shale	1640		
shale	465	sand	1665		
lime	470	shale sandy	1680		
shale	475	shale	1710		
shale & shells	505	lime	1715		
sand	515	shale	1725		
shale	535	lime	1755		
lime	540	shale	1780		
shale	560	lime	1850		
lime shells	570	water sand	1860		
red rock	575	lime	1972		
shale	585	shale	1975		
lime	595	MEAS. CORR.	1985		
shale	605	shale	2050		
lime	610	shale sandy	2070		
shale	615	shale	2125		
lime	620				
shale	700	lime	2244		
lime	705	shale black	2248		
shale	720	lime	2257		
lime	725	shale	2260		
shale	760	lime	2305		
lime shells	770	shale & lime	2325		
shale	790	lime	2345		
lime	820	shale	2374		
shale	840	lime	2382		
lime	845	shale-cvg.	2400		
shale	850	shale & lime	2410		
lime	890	shale	2425		
shale sandy	900	lime	2445		
lime	905	shale	2485		
shale	940	lime	2490		
		lime broken	2515		
		shale	2525		
		lime	2540		

WATER RECORD

4 BWPH @ 280-290
1 1/2 BWPH @ 510
1 BWPH @ 920
1 1/2 BWPH @ 1140
2 BWPH @ 1280
HFW @ 1850-1860
12 BWPH @ 2765
1 BWPH @ 2863-2871
2 BWPH @ 2975
Hole filled 200'
with water in 1 hour
@ 3183 - T. D.

TOPS:

Meas. Corr 1985
K. C. Lime 2125
Mississippi 2729
Arb. Lime 3177