


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - KEWANEE OIL CO.  
Farm Crowley No. 1

SEC. 11 T. 28 R. 5 E  
SEc SW  
330' fSL 330' fEL of SW/4

Total Depth. 2700'  
Comm. 3-1-46 Comp. 3-28-46  
Shot or Treated. Shot w/40 qts. 3-30-46  
Contractor. Rex & Morris Drlg. Co.  
issued. 8-17-46

County. Butler  
KANSAS



CASING:

15 1/2" 340' P 8 3/4" 2320' P  
13 3/8" 955' P 7" 2685' Cem.  
10" 1862' P

Elevation. 1293

Production. Pmpd 168 BO &  
10 BW after shot

Figures Indicate Bottom of Formations.

cellar	0-7	shale	1325	Swabbed approx. 1 1/3
lime	45	lime	1340	BO Natural per hr.
shale	70	shale	1345	Pumped 168 BO & 10 BW after
lime	80	shale & shells	1370	shot in 24 hrs.
shale	95	lime 1/2 BWP	1395	
red rock	100	shale	1455	Shot 3-30-46 w/40 qts. solidified
lime	135	lime brkn	1465	Nitroglycerine from 2691'
shale	145	lime	1505	to 2700'.
red rock	155	shale	1525	
lime	160	lime	1535	
shale	170	shale	1565	
lime	185	lime	1570	
shale	260	shale	1610	
lime	275	shale sdy	1660	
shale	285	1/2 BWP 1625-30'		
lime	300	shale	1710	
1 BWP 290-300'		lime	1715	
shale	305	shale	1730	
red rock	310	lime	1760	
shale & shells	340	shale	1785	
shale	345	lime	1970	
shale & shells	425	1 BWP 1850'		
shale	450	1/2 BWP 1945-55'		
shale & shells	485	shale & shells	2000	
shale	580	shale	2112	
lime	590	lime	2228	
red rock	595	show oil 2124-26',		
shale	690	no gas		
shale sdy 2 BWP	700	shale	2230	
shale	795	lime	2262	
lime	815	shale	2265	
shale	830	lime	2280	
shale & shells	855	shale sdy lime 3 1/2 BWP	2290	
lime	875	lime	2310	
shale	885	shale	2335	
lime	890	lime	2340	
shale	920	shale	2375	
sand 1 BWP	930	shale & shells	2400	
shale	945	shale	2420	
lime	950	lime	2430	
shale	1005	shale	2440	
lime	1020	shale & shells	2480	
shale	1025	lime brkn	2500	
lime	1030	shale	2510	
shale	1035	lime	2530	
shale & shells	1055	shale	2665	
shale	1130	shale gy sdy	2680	
lime	1165	SLM Corr: 2685'		
shale	1185	shale gy sdy	2689	
lime	1210	sand oil	2700	
1/4 BWP 1200'		Total Depth.		
shale	1230			
lime	1255	Tops:		
shale	1260	Lansing	1785	
lime	1305	Btm. Lansing	1970	
1/4 BWP 1300'		K. C. lime	2112	
shale	1310	Btm. K.C. lime	2228	
lime	1320			