

25-14-15W

Plotted Texas Co.

THE HARTMAN-BLAIR OIL CO.
B.S. Harbaugh No. 3.


SEC. 25 T.14 R.15W
NE SE SW

Total Depth. 3152'
Comm. 7-22-36 Comp. 9-13-36
Shot or Treated,
Contractor. Exchange Drlg.Co.
Issued. 10-17-36

County. Russell

CASING:
20 " 32'6"
15 1/2" 303'
12 1/2" 455'
10 " 755'
8 1/4" 2464'
6 5/8" 2912'
5 3/16" 3143'
20' of 4" lines.

OCT 17 1936



Elevation.

Production. Pot. 1307 B.

Figures Indicate Bottom of Formation.

surface	30	lime	1535	lime hrd	2830
gravel	35	shale	1540	lime	2852
shale blue	55	shale shells	1560	shale	2870
shale light	100	lime	1595	lime	2887
white	140	shale light	1610	red rock	2890
sand	155	brkn lime	1660	shale blue	2910
sand s.lime	175	red rock	1670	lime	2925
shell	178	lime	1800	shale b.	2931
red rock	185	shale blue	1810	lime	2952
shale white	195	lime	1830	oil pay 2934-40	
shale blue & shells	215	shale	1840	3 BPH 2952	
shale blue	225	lime	1920	lime	2974
shale light	255	shale blue	1925	3 BO 2965	
mud blue	270	red rock	1930	shale	2977
shale blue	283	brkn lime	1960	lime	2995
sand	295	lime	2000	lime hrd	3005
shale blue	320	red rock(hole cavng)	2010	brkn lime	3010
sand water	360	lime	2065	lime	3015
red rock	410	shale b	2075	lime hrd	3020
shale	415	red rock	2085	brkn lime	3025
lime	420	lime	2090	lime SO 3068	3088
lime & shale brks	425	lime hrd caving	2110	HFV 3075-81	
lime	435	lime	2120	red rock	3090
sand	445	shale	2125	lime caving	3100
red rock	455	lime	2135	shale blue	3103
red rock	742	brkn lime	2165	lime hrd	3106
lime	745	shale blue	2175	lime not so hrd	3115
HFV 705		shale & shells	2265	shale blue	3120
lime	780	red rock cave	2270	lime	3144
red rock	825	shale b & shells	2280	shale green	3148
lime	850	red rock	2305	Correction-3148=3143 SIM	
red rock	870	shale blue cavng	2315	lime	3145
lime	885	lime	2320	sand	3152
red rock	935	shale & shells	2385	SO 3046-48	
lime shells	955	shale	2420	1000' 30 min. 3048-52	
shale blue	990	lime hrd	2430	best pay 3051-52	
red rock	1030	shells & shale blue		Total Depth	
shale blue	1050	breaks	2465		
lime	1070	shale	2485		
shale blue	1090	lime	2520		
lime	1120	shale	2560		
lime shells&shale		lime	2563		
breaks	1170	shale	2570		
salt	1425	lime	2610		
shale b.	1435	shale	2615		
lime grey	1465	shale	2626		
lime	1480	lime caving	2650		
shale white	1495	slate b. cave	2655		
lime	1505	lime	2805		
shale	1510	lime sdy	2825		