

G.E. Jamison
25-14-15W


HARTMAN AND BLAIR OIL CO.
Harbaugh No. 7

SEC. 25 T. 14 R. 15W.
SW NE SW

Total Depth. 3176
Comm. 9-4-37 Comp. 11-10-37
Shot or Treated.
Contractor. Saco Oil Co.
Issued. 1-15-38

County Russell.

JAN 15 8 1938



CASING.

15 1/8" 310'
12 1/2" 465'
10" 753
8 1/4" 2646

Elevation.

Production. Pot. 1898 B.
Scout report.

Figures Indicate Bottom of Formations.

soil	10	shale grey	1955	rod rock	2912
clay yellow	25	lime light	1965	shale dark	2925
sand	48	rod rock	1975	shale	2930
shale blue	58	lime light	1990	show oil 2945-54	
shale light HFW	165	rod rock	2000	show oil & gas 3075	
sand	170	lime	2010	oil at 3081-6"-3086	
rod rock	180	shale light	2018	lime	3080
mud blue	210	broken lime	2035	correction 3080= 3086'6"	
shale light	250	shale light	2050	lime	3100
shale light	255	rod rock	2060	water 3100-05 hole filled	
shale blue	290	lime	2075	600' in 8 hrs.	
sand	305	shale dark	2090	7 1/2 Bailors water in 8 hrs.	
shale blue	325	shale	2100	probably from behind pipe.	
sand	330	lime	2120	oil from 3081'6" to 3068	
sand red	340	bad hole		(steel line)	
rod rock	530	shale blue	2140	shale var.	3117
sand red	535	lime	2150	2 coils water 3095-3100	
5 BW		shale dark	2160	free oil 3100 to 3110	
rod rock	610	lime	2175	(3106 to 3116) Steel line	
sand HFW	630	shale cave	2190	measurement) lime shows	
12 BWPBR 630-685		shale dark	2200	saturation 3100 to 3110	
rod rock	745	lime	2202	3106 to 16 (corrected S.L.	
anhydrite	753	shale	2210	5 coils on sand reel oil	
lime	775	shale blue	2250	and water from 3100 to 3116	
anhydrite lime white	785	shale dark	2275	lime	3122
rod rock	945	lime	2285	bailing out water.	
shale blue	995	shale light	2315	lime	3137
rod rock	1060	lime	2320	shale light	3148
shale dark	1120	rod rock	2322	lime	3164
salt	1280	shale dark	2335	hole caving bad 3164 to	
shale blue	1285	shale	2365	3128	
salt	1300	shale dark	2370		
salt grey	1355	lime	2375	lime	3175
salt	1450	shale blue	2385	3164 to 3128 corrected	
shale blue	1470	lime	2400	by acid bottles.	
lime light	1475	shale light	2405	lime	3176
shale blue	1485	lime	2409	caving. bailing water	
lime broken	1545	shale dark	2445	3176 steel line measurement.	
rod rock	1555	lime	2465	Total Depth.	
lime	1565	shale dark	2470		
shale light	1585	lime	2480		
rod rock	1600	shale dark	2485		
broken sdy lime blue	1635	lime	2490		
shale light	1650	shale dark	2515		
shale light sholly	1690	lime	2519		
rod rock	1720	shale light	2525		
lime	1740	lime	2530		
lime light	1750	shale dark	2615		
shale light	1765	lime	2628		
lime	1840	shale light cave	2640		
shale blue bad hole	1845	lime	2645		
rod rock	1860	shale	2655		
shale blue	1870	lime	2872		
lime	1890	shale blk	2875		
shale light	1900	lime	2900		
lime	1910	shale	2905		
shale light	1950	lime	2907		