

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

503 E. Murdock

Wichita, Kansas

25-14-15W

Company - HARRY GORE
Farm - Harbaugh

No. 10

SEC. 25
CSL NW SW

T. 15

R. 15W

Total Depth. 3189

Comm. 6-5-49

Shot or Treated.


Contractor. Harry Gore

Issued. 9-10-49

Comp. 8-12-49

County. Russell

KANSAS



CASING:

12 1/2" 135' P.
10 3/4" 806' cem. w/1200 sx.
8 5/8" 2494' P.

7" 3184 cem. w/100 sx. Elevation. 1768 *and*

Production. 100 bbls.

Figures Indicate Bottom of Formations.

cellar	10	shale gry	1855	lime	2886
shale blue	50	lime	1880	shale blue	2892
shale sdy	76	shale ry	1900	lime hrd	2896
sand	80	lime brkn	1945	shale blue	2907
shale gry	170	red rock	1950	lime Dodge	2922
sand	190	lime	1965	shale	2949
slate wh	195	shale gry	1980	SO 2960-65	
shale blue	200	lime	2000	SSO 2971-25	
shale yllw	210	lime brkn	2040	SO 3000-05	
shale blue	275	red rock	2060	70 at 3185 FU 100'	
sand	285	shale blue	2070	in 30 min.	
shale blue	315	lime, shells	2105	K.C. lime	3039
sand	330	red rock	2115	lime sft	3045
shale blue	345	shale & shells	2140	shale blue	3050
sand	405	shale blue	2150	lime	3122
red rock	792	shale & shells	2215	red rock	3125
anhyd. lime	828	shale blue	2240	lime	3150
shale blue	840	lime	2248	shale blue	3158
red rock	900	shale	2255	lime	3173
shale blue	925	lime brkn	2265	shale	3177
shale rn	940	shale blue	2293	lime sdy	3185
shale blue	960	lime	2305	sand Gorham	3189
red rock	985	shale blue	2310	Total Depth	
shells & shale	995	shale blue	2340		
shale blue	1055	red rock	2345	Hole filled up in 20	
red rock	1100	shale gry	2367	hrs w/1,950' oil & wtr.	
shale gry-	1120	lime	2372		
shale blue	1175	shale blue	2408	Tops:	
shale blue & shells	1195	lime	2423	Anhyd.	792
shale blue	1230	shale blue	2440	Dodge lime	2907
salt	1235	shells & shale	2480	K.C. lime	2949
salt brkn	1275	shale blue	2485	Gorham sand	3185
salt	1360	lime brkn	2490		
slate & shells	1400	shale blue	2494	Water Record;	
lime	1430	lime	2500	1 BWPH 50-55	
shale gry	1435	lime, shells	2508	10 BWPH 100	
lime	1453	lime	2523	5 BWPH 170-180	
lime brkn	1475	slate gry	2533	HFV 180-190	
lime	1505	lime	2535	Water 345-360	
shells & shale	1530	shells & shale	2550	HFV 445-450	
lime hrd	1542	shale blue	2568	2 BWPH 840 squeezed	
lime & shale	1562	lime	2573	off wtr w/150 sx. cem.	
shale blue	1575	shale blue	2600	1/2 BWPH 2007-2014	
red rock	1595	lime hrd	2605		
lime	1605	lime brkn	2660		
shale	1620	lime hrd	2680		
lime & shale	1635	lime brkn	2685		
shale blue	1650	lime sdy	2746		
lime	1670	shale blue	2748		
lime brkn	1685	lime	2750		
shale blue	1690	shale blue	2755		
red rock	1700	lime	2800		
shale blue	1720	lime & shale	2815		
lime	1730	lime sharp	2825		
lime, shells	1763	shale blue	2830		
lime hrd	1773	lime	2845		
lime, shells	1775	lime sharp	2855		
shale blue	1780	lime	2865		
lime	1815	lime sharp	2875		
lime sdy	1840				
		shale blue	2892		
		lime hrd	2896		