


10" 582 FARM Rarick
 8 1-4 1290 COMPANY R. G. Gillespie
 15 1-2 6 5-8 CONTRACTOR
 12 1-2 563 5 3-16 COMMENCED Aug. 13, 1925.
 TOTAL DEPTH 1345' SHOT 40 QUARTS BETWEEN
 CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO

NO. 1 COUNTY Elk

22-31-10E



ELEVATION

INITIAL PRODUCTION

180 bbl.

FIGURES INDICATE BOTTOM OF FORMATIONS.

REMARKS 1/29/27.

Formation	Depth	Formation	Depth
soil	5	shale	1190
shale	10	lime	1220
lime	55	shale	1224
shale	75	sand	1265
lime	90	shale	1269
shale	115	lime	1290
lime	130	Show oil	1294
red rock	140	black shale	1304
lime	160	lime	1325
shale	240	oil	1345
sand	265	Little water	1345
shale	293	Plugged with wool lead back	
lime	311	to 1343 $\frac{1}{2}$	
red rock	331	Total Depth	1345'
water sand	351	<u>DEEPENING RECORD</u>	
lime	367	Started May 5, 1926.	
red rock	382	Completed May 17, 1926.	
shale	450		
water sand	475	lime	1376 1/2
lime	480	shale	1397
water sand	495	lime	1402
lime	498	sand	1420
water sand	506	shale	1435
shale	585	lime	1470
lime	589	shale	1485
shale	600	sand (5 B. W.)	1495
lime	608	shale	1540
shale	628	lime	1565
lime	634	shale	1608
sand	639	lime SIM set 6 5/8" csg.	1610
shale	660	lime (showing oil)	1613
lime	668	sandy lime	1624 1/2
shale	775	lime	1626
lime	850	(showing a little water)	
shale	852	Total Depth	1624
lime	885		
shale	975	Plugged back with wool lead to	
lime	1025	1624-1/2	
shale	1047		
lime	1051	6 5/8" x 8 1/4" Screw Anchor	
shale	1105	packer set at 1360' to shut off	
lime	1134	water and protect oil sand 1325 to	
shale	1152	1343 1/2.	
lime	1164		
shale	1166	Record of shooting Walter Rarick	
lime	1186	No. 1, shot January 3, 1927 with	
		20 qts from 1617 to 1623'.	