

WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY  
UNION NATIONAL BANK BLDG., WICHITA, KANSAS


## CASING RECORD

LOCATION

SE cor NE SE

SEC 22 T 31 R10 E

20" 10" 400' FARM Rarick NO. 4 COUNTY Elk  
 15 1-2 8 1-4 829 COMPANY R. G. Gillespie.  
 12 1-2 6 5-8 1345' CONTRACTOR  
 5 3-16 COMMENCED Oct. 22, 1925. COMPLETED Nov. 13, 1925.  
 TOTAL DEPTH 1375' SHOT 60 QUARTS BETWEEN  
 CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO



ELEVATION

INITIAL PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS.  
REMARKS 1/29/27.

Formation	Depth	Formation	Depth
sand	3	sand	1329
shale	30	lime	1341
lime	110	shale	1345
shale	130	lime	1353
lime	145	Oil show	1368
shale	170	sandy lime	1374
lime	185	sandy lime	1375
red rock	195	Total Depth	1375'
lime	215		
shale	265		
sand	290		
shale	305		
lime	325		
shale	350		
lime	355		
shale	365		
lime	370		
sand	385		
lime	398		
red rock	400		
lime	402		
red rock	407 ?		
lime	429		
shale	439		
red rock	455		
shale	470		
lime	475		
shale	610		
lime	625		
sand	630		
shale	665		
lime	672		
shale	677		
lime	679		
water sand	696		
shale	818		
lime	882		
shale	887		
lime	950		
shale	1070		
lime	1075		
shale	1131		
lime	1134		
gas sand	1176		
gas	1147		
shale	1186		
lime	1191		
shale	1208		
lime	1250		
sand	1307		
lime	1322		
sand	1324		
lime	1326		

DEEPENING RECORD

Started June 5th, 1926.

Completed June 29th, 1926.

lime	1402
shale	1407
lime	1425
shale	1495
lime	1510
shale	1518
lime	1524
shale	1546
sand	1566
sandy lime	1598
(Set 5 3/16" csg. at 1504')	
lime	1607
shale	1611
lime	1630
shale	1647
lime	1651
Oil	1655
sandy lime	1656
(Showing some water)	
Plugged back to 1655' with wool lead.	

Shot with 5 quarts June 17, 1926.

Shot with 10 " " 21, 1926.