

PLOTTED
G. E. Jameson

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.


DILLER OIL & GAS CO.
Cochran No. 2

25-31-10E
SEC. 25 T. 31 R. 10E.
NW SW

Total Depth. 2283
Comm. 3-4-37 Comp. 4-19-37
Shot or Treated.
Contractor.
Issued, 4-2-38

County Elk.

APR 2 1938



CASING.

12 1/2" 479'
10" 728'
8" 1338'
65/8" 2017'
53/16" 2272'

Elevation.

Production. Est 50 B.

Figures Indicate Bottom of Formations.

soil	10	sand	1310
gravel	15	shale	1320
shale	25	sd shale	1333
lime	30	lime	1440
shale	40	shale	1465
lime	85	lime	1470
shale blue	90	shale	1495
red rock	95	shale	1515
broken lime	115	lime	1525
red rock	125	shale	1550
shale	140	sand (sh oil some wtr)	1570
lime	170	broken sd lime	1600
shale	180	shale	1615
lime	195	lime	1650
shale water	260	shale	1670
sd lime water	295	lime	1698
shale	325	show 1675-1685	
lime	355	shale blk	1703
shale blue	360	lime	1712
red rock	365	shale	1772
shale blue water 390	385	lime H.	1775
sd shale	400	shale	1890
lime	420	red rock	1895
shale	435	shale	1935
red rock	458	red rock	1945
shale blue	478	shale	1995
lime	480	Gas 1997 show oil	1999
shale	490	chat	2017
sd lime	500	lime	2135
shale	610	lime blk	2232
lime water 615	630	lime white	2239
shale	653	shale blue	2241
sd lime	665	shale blk	2250
lime	690	shale	2272
sd lime	705	shale blk	2281
shale	710	lime	2283
lime	715		
shale	865		
shale	895		
lime	905		
shale	915		
lime	925		
shale	1040		
shale shelly	1070		
shale	1100		
lime	1105		
shale	1120		
lime shells & shale	1135		
sd lime	1180		
lime	1210		
shale	1240		
lime	1275		
sand	1290		
shale	1300		

oil Penn

oil F. Scott

Miss

Total Depth.

WATER RECORD.

4 BWPHR 260-295

3 BWPHR 480-500

1 BWPHR 1170-1175

Hole full 2125-2135

OIL AND GAS RECORD.

oil 1555

oil 1675-1685

gas 1997

oil 1999

oil from 2282-2283 Oil

filled up to top at 600' per

hour. Pay sand 2282'6-2283