

Plotted
milled

26-31-10E

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

MAY 29 1933

Location. CNL NE SE
330' S 660' W. SE 1/4

Sec. 26 T. 31 R. 10E.

Casing Record. 10" 345 Farm. Clifford J. Hull No. 1

County. Elk

20" 8 1/2" 725 Company. John Croft et al.


15 1/2" 65/8" 1333 Contr.

12 1/2" 53/16" Comm. 3-15-33

Comp. 5-22-33

Total Depth. 1710 Shot Quarts Between.

Correspondence Regarding This Well Should Be Referred To.



Elevation.

Figures Indicate Bottom of Formations.

Initial Production. DRY

Date Issued. 5-27-33

| Formation | Depth | Formation | Depth. |
|---------------|-------|-------------------------|---------|
| soil | 4 | shale | 930 |
| lime | 75 | lime | 950 |
| shale | 85 | shale | 1080 |
| red rock | 90 | lime | 1082 |
| lime | 100 | shale | 1135 |
| red rock | 107 | sand show oil | 1150 |
| lime | 112 | lime 2 BW | 1185 |
| red rock | 120 | shale | 1195 |
| lime | 150 | lime | 1225 |
| shale | 154 | sand 4 BW | 1287 |
| lime | 156 | shale | 1297 |
| shale | 165 | shale sdy | 1323 |
| red rock | 175 | lime | 1427 |
| lime | 180 | shale | 1505 |
| shale | 190 | lime | 1522 |
| lime sdy | 222 | shale | 1524 |
| shale | 275 | lime | 1529 |
| lime | 280 | shale | 1539 |
| shale | 328 | sand Peru | 1585 |
| lime | 340 | showed oil 2 BW 1562-72 | |
| 5 BW 325-35 | | shale | 1604 |
| shale | 345 | lime | 1638 |
| lime | 350 | shale | 1658 |
| shale | 370 | lime OSWEGO | 1685 |
| sand 4 BW | 390 | no oil or water | |
| lime | 400 | shale | 1710TD. |
| shale | 415 | | |
| lime sdy 1 BW | 440 | | |
| shale | 600 | lime sdy 1 BW | 750 |
| lime | 615 | shale | 870 |
| shale | 635 | lime | 880 |
| lime sdy | 645 | shale | 885 |
| shale | 655 | lime hard | 897 |
| sand | 671 | shale | 902 |
| shale | 674 | lime | 915 |
| lime | 680 | | |
| shale | 700 | | |
| sand wtr | 715 | | |
| shale | 725 | | |