

12699

WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY  
BITTING BLDG., WICHITA, KANSAS

CASING RECORD

LOCATION NW NW NW

SEC 26 T 31 R 10E

10" 436 FARM John D. Waller NO. 1 COUNTY Elk  
20" 8'-4 817 COMPANY Theta Oil Company.  
15 1-2 6 5-8 1332 CONTRACTOR W.F. Braden  
12 1-2 15 5 3-16 COMMENCED COMPLETED



TOTAL DEPTH 1366 SHOT 70 QUARTS BETWEEN 1349-1354

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO Theta Oil Company.

76 West Monroe, Chicago, Ill.

ELEVATION

FIGURES INDICATE BOTTOM OF FORMATIONS.

INITIAL PRODUCTION 25 bbls.

REMARKS

Formation	Depth	Formation	Depth.
soil dark soft	8	shale light soft	602
lime shells hard	13	lime hard	606
lime hard	38	shale blue soft	626
shale dark soft	42	lime hard	632
lime hard	50	sand hard	637
shale dark soft	58	shale white soft	654
lime hard	66	sand	680
shale dark soft	76	shale soft	804
lime hard	80	lime	926
red rock soft	85	shale dark soft	961
lime hard	97	shale white hard	1016
shale black soft	102	shelly lime	1076
red rock soft	127	shale blue soft	1125
lime hard	147	lime hard	1155
shale soft	150	shale	1170
lime hard	162	lime	1210
shale black soft	167	sand	1290
lime shells hard	182	lime	1305
sandy shale soft	202	shale	1308
shale black soft	232	lime	1319
sand soft	247	shale	1328
shale light soft	275	lime	1330
sand sharp	295	lime	1354
shale soft	317	lime	1358
lime hard	333	lime	1365
shale dark soft	337	lime	1366
lime hard	340		
shale dark soft	345	Water sands 275-295 Hole full	
red rock soft	360	1285-1290 Hole full. 654-680 4 B.W	
sand hard	375		
shale blue soft	384	Pay sands	
lime gray hard	383	1351-1365	
shale dark soft	415		
red rock soft	430	Bottom of hole 1366 but plugged back	
shale dark soft	436	to 1365 with lathe shavings and	
lime gray hard	440	lead wool	
shale dark soft	460	Deepened as follows	
lime gray hard	464	Drilling commenced Apr 9, 1926	
sand soft	473	lime	1395
shale dark soft	484	shale dark	1420
sand white soft	492	shale light	1475
		lime	1500
		shale sdy	1525
		sd	1533
		sd	1551
		small show oil	
		sand	1576
		shale blk	1590
		lime	1612
		shale blk	1630
		top of pay sand	
		lime sdy	1639

First show very small 1633  
First pay 1635 to 1637  
second pay 1638-1639  
water in last foot pay.