

WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY
UNION NATIONAL BANK BLDG., WICHITA, KANSAS

CASING RECORD

LOCATION NE NW NW ?

SEC 26 T 31 R 10E

20" 10"
15 1-2 8 1-4
12 1-2 6 5-8
5 3-16

FARM J. D. Waller
COMPANY Theta Oil Company.
CONTRACTOR

NO. 3 COUNTY Elk

COMMENCED Dec. 27, 1926. COMPLETED Jan 21, 1927.

TOTAL DEPTH 1661'

SHOT QUARTS BETWEEN

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO Theta Oil Company,

Madison, Kansas.

FIGURES INDICATE BOTTOM OF FORMATIONS.

ELEVATION
INITIAL PRODUCTION

REMARKS 1/29/27.



Formation	Depth	Formation	Depth
soil	8	lime	682
rock	11	sand	690
shale	17	shale (Set 10" csg. at 692')	825
slate white	40	lime (Showing of gas at 835')	860
lime	70	shale	875
shale	74	lime	950
lime	80	shale	1145
slate	100	lime	1170
red rock	105	shale	1180
lime	115	lime	1190
shale	123	shale	1197
red rock	143	lime	1225
lime	158	sandy lime Water at 1255'	1250
slate white	208	sand HFW at 1280'	1300
sandy shale	260	sand hard	1340
sand (5 B. W.)	285	shale black	1350
lime	295	(Set 8 1/4" csg. at 1350')	
slate white	320	lime	1375
lime	340	lime brown	1420
sandy shale	350	shale black	1450
lime	366	shale white	1490
black shale	370	shale dark	1495
lime hrd	375	lime hard	1520
red rock	381	shale	1527
sand	395	lime	1535
(Set 12 1/2" csg. 395')		shale sandydark soft	1565
shale	405	sand Peru-No oil	1603
lime	409	shale dark	1610
shale	420	lime Oswego lime	1632
r.d rock	435	(Set 6 5/8" csg. 1612')	
shale light	465	shale dark	1653
lime	471	lime	1661
shale	485	(First show 1657-1660')	
sand HFW	540		
shale	543		
lime	561	TOTAL DEPTH	1661'
shale	625		
lime	629		
shale	647		
lime	652		
sand (Water sand)	672		
shale	677		