


34-31-10E

20" 10'666 FARM Lisco
 15 1-2 8 1-4 1334 COMPANY Theta Oil Co.
 1-2 398 6 5-8 CONTRACTOR Frank Young
 TOTAL DEPTH 5 3-16 COMMENCED Sept 21, 1926

NO. 1 COUNTY Elk
 COMPLETED Nov 4, 1926
 QUARTS BETWEEN



CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO Theta Oil Co.
 Moline Kansas.

ELEVATION 107

FIGURES INDICATE BOTTOM OF FORMATIONS.
 REMARKS 12-11-26

INITIAL PRODUCTION 100 bbls.

Formation	Depth	Formation	Depth.
soil	8	Oswego lime	1684
lime	16	shale blk	1690
shale blue	20	lime	1700
lime	50	shale blk	1770
shale light	55	shale white	1870
lime	85	redrock	1880
shale blk	90	shale white	1925
lime	94	red rock	1930
shale blue	99	shale blk	1984
red rock	106	lime	1985
lime	116	show gas 1990	
shale white	125	shale green	1996
red rock	135	set 6-5/8 1996	
shale blue	280	Miss lime	2080
1 bailers water per hr	265	sand	2120
lime white	293	HFW 2090	
shale blue	320	lime	2240
lime white	350	shale light	2245
shale blk	365	shale blk	2283
rock set 12 1/2 398	405	6-3/16 2282	
lime	415		
shale	475	top wilcox	2283
sand	510	oil	2285
shale white	612	T.D.	2285
lime sdy	622		
shale light	635		
lime	640		
sand	655		
set 10 "casing 666			
shale white	715		
shale sdy	830		
lime	855		
shale brown	870		
lime	930		
shale white	960		
lime shelly	960		
shale blk	970		
shale white	1070		
lime	1090		
shale sdy	1125		
sand	1160		
lime	1260		
sand HFW 1330	1330		
lime	1355		
slate blk	1363		
lime	1425		
shale blk	1440		
shale white	1505		
lime	1535		
shale	1545		
sand	1580		
shale sdy	1612		

3260
 1996
 244

lime	1633
shale	1634
lime	1638
slate blk	1653
shale white	1684