

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas


35-27-8 E

BEAUMONT PETRO.CO.
Lewis "A" No. 19.

SEC.35 T.27 R.8 E
CSW NE

Total Depth. 2728'
Comm. 10-2-42 Comp. 11-9-42
Shot or Treated.
Contractor. Self
Issued. 2-13-43

County. Greenwood



CASING:

12 $\frac{1}{8}$ " 908' P 7" 2044' P
105/8" 1187' P 53/16" 2536' P
85/8" 1512' P

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

floor to surface	2	shale	1045	shale	SLM	2668
cellar	6	lime	1050	lime blk		2693
lime	28	shale	1100	lime gy		2695
shale	35	lime	1140	sand-wtr		2706
lime	58	shale	1152	lime		2728
red rock	60	red rock	1165	Total Depth.		
lime	70	lime	1170			
shale	75	shale	1175			
lime	85	lime	1190	Formation Tops:		
shale	105	shale	1255	KC lime 1750		
lime	125	sand	1270	Peru 1956		
shale	135	shale dk	1285	Miss. lime 2547 SLM		
lime	160	shale	1393			
shale	170	lime	1398	1 BW hr 325-30		
lime	180	shale	1410	2 BW hr 525-35		
shale	185	lime	1430	(14"x15' bailer)		
shale&lime shls	230	shale	1470	HFW 1252-70		
shale	240	lime	1630	3 BW hr 1850-58		
red rock	245	shale sdy	1675	(7" x 31' bailer)		
shale	255	shale	1750	HFW 1975-85		
red rock	257	shale-lime shls	1770	$\frac{3}{4}$ BW hr 2095-2100		
lime	265	lime	1780	(5 $\frac{1}{4}$ " x 38')		
shale	285	shale	1790	HFW 2549-54		
lime	300	lime	1915	HFW 2695-2706		
shale dk	315	shale	1920			
shale sdy	340	lime	1948	good sh oil		
shale	360	sand	1959	1956-67 SLM		
lime	365	(Corr.SLM 1967)		lgt sh 2160-65		
shale	371	sand	1970			
lime	375	sdv wtr	2000			
shale	410	shale & sand	2035			
lime	415	shale	2087			
shale	445	lime	2100			
lime	455	shale	2125			
shale	470	lime	2135			
lime	540	shale dk	2140			
shale	595	shale sdy	2150			
lime	605	sand	2165			
shale	620	SO 2160-65				
lime	655	shale & sand	2205			
shale	675	lime	2268			
lime	685	shale sdy	2300			
shale	690	shale	2315			
lime	720	lime shls	2330			
shale	760	shale	2354			
lime	770	lime	2375			
shale	775	shale	2390			
lime	805	sdv lime	2395			
shale	810	shale	2437			
lime	850	red rock	2440			
shale	860	shale bkn	2465			
lime	880	shale lt	2470			
red rock	895	shale lime shls	2515			
shale	907	shale	2535			
lime	912	lime	2536			
shale	917	(Corr. SLM 2547)				
lime	930	lime & sand	2549			
shale	940	wtr sand	2554			
lime	965	lime	2574			
shale	1000	lime gy hd	2579			
lime	1010	lime blk	2665			